



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-065-20590-00-00

RECEIVED
STATE CORPORATION COMMISSION
FEB 12 1973
02-12-1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Joe Weber of Abercrombie Drlg. Co., Inc., has this date requested permission to plug the following described well:

Mr. Weber guarantees payment of the plugging fee.

Operator's full Name: Tomlinson Oil Company, Incorporated,

Complete Address: Suite-1030, 200 West Douglas, Wichita, Kansas.

Lease Name: Masters Well No. 1

Location: NW-NW-NW Sec. 32 Twp. 10 Rge. (E)(W) 21

County: Graham Total Depth 3975' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Weber was instructed to plug the well as follows:

217'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota formation @ 650'.

Circulate hole with heavy mud. Pull DP to 875' and displace 110 Cu. Ft. cement thru DP. Pull DP to 245' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

H. G. Nichols
Conservation Division Agent