

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JAN 26 1973
01-26-1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-065-20583-00-00

Operator's Full Name National Oil Company,

Complete Address Garvey Building, Wichita, Kansas.

Lease Name Acheson Well No. 1

Location SE-SW-SE Sec. 21 Twp. 10 Rge. (E) (W) 21

County Graham Total Depth 3828'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Woodman-Iannitti Drilling Company,

Address 706 Union National Bank Building, Wichita, Kansas License No.

Operation Completed: Hour 1:30 AM Day 20 Month 1 Year 1973

The above well was plugged as follows:

223'--8 5/8" Surface casing, cement circulated with 135 Sx.
Top of Dakota section @ 575'.

Circulated hole with heavy mud.--Pulled-DP to 800'-and-displaced-110 Cu.-Ft. cement
thru DP from 800' to 475'. Pulled DP to 245' and displaced 30 Cu. Ft. cement thru DP
from 245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement
to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. G. Nichols
Well Plugging Supervisor

DATE 1/30/73
INV. NO. 6905-W