

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-065-00103-00-01

RECEIVED
STATE CORPORATION COMMISSION
NOV 1 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Petroleum, Incorporated,

Complete Address: 300 West Douglas, Wichita, Kansas.

Lease Name Acheson Well No. 1

Location NE-NE-NW Sec. 21 Twp. 10 Rge. (E) (W) 21

County Graham Total Depth 3849'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: This well was a WASHDOWN

Plugging Contractor: Garvey Drilling Company,

Address: Rte. #2, Great Bend, Kansas. License No.

Operation Completed: Hour 2:00 AM Day 31 Month 10 Year 1968

The Above well was plugged as follows:

121'--8 5/8" Surface casing, cement circulated.
Top of Dakota section @ 875'.

Circulated hole with heavy mud. Pulled DP to 1100' and displaced 100 Sx. cement thru
DP from 1100' to 775'. Pulled DP to 150' and displaced 20 Sx. cement thru DP from 150'
to 90'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of
cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *H. L. Nichols*
Well Plugging Supervisor

INVOICED

DATE 11/1/68
INV. NO. 8739-W