

KANSAS

Form CP-3  
Rev. 6-4-68

*SP*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

FEB 12 1973  
02-12-1973  
CONSERVATION DIVISION  
Wichita, Kansas

15-065-20590-00-00

Operator's Full Name Tomlinson Oil Company, Incorporated,

Complete Address Suite-1030, 200 West Douglas, Wichita, Kansas.

Lease Name Masters Well No. 1

Location NW-NW-NW Sec. 32 Twp. 10 Rge. (E) (W) 21

County Graham Total Depth 3975'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Abercrombie Drilling Company, Incorporated,

Address 801 Union Center, Wichita, Kansas. License No.       

Operation Completed: Hour 10:15 AM Day 3 Month 2 Year 1973

The above well was plugged as follows:

217'--8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section @ 650'.

Circulated hole with heavy mud. Pulled DP to 875' and displaced 110 Cu. Ft. cement  
thru DP from 875' to 550'. Pulled DP to 245' and displaced 30 Cu. Ft. cement thru  
DP from 245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *M. L. Nichols*  
Well Plugging Supervisor

DATE 2/12/73

INV. NO. 6969-w