

15-065-00441-00-00

B

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 55-35

LOCATION NW SE NW

SEC. 33 TWP. 10 RGE. 21

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. C-1 Lease Noah

Operator Petroleum Inc Address 311 E 3rd Wichita, Kans

Field _____ County Graham

Total Depth 3830 Feet.

Plugging Contractor Morgan Pipe Pulling

Plugging Contractor's License No. 43

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 209' circulated with cement - 5 1/2" at 3825' with

75 sax cement behind - P.B. to 3540, perforated at 3518'.

Filled with chat to 3500', set 4 sax cement with dump bailer,

pulled 1100' 5 1/2" - heavy mud to 200', set rock and 15 sax

cement, mud to 35', set rock and 10 sax cement to bottom cellar.

Edwin J. [Signature]
District Conservation Agent
STATE CORPORATION COMMISSION

Date 6-12-56
JUN 14 1956

CONSERVATION DIVISION
Wichita, Kan.

06-14-1956

PLUGGING
FILE SEC. 33 T. 10 R. 21 W
BOOK PAGE 55 LINE 35