

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Hartman Oil Co., Inc.
Address: 12950 E 13th St. N - Wichita, Ks. 67230-1457
Phone: (620) 277-2511 Operator License #: 30535
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 6/18/08 as per Steve Durant (Date)
by: Witness by Ken Jehliik (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
St. Louis Depth to Top: 4753' Bottom: 4753' T.D. 4764'
Morrow Depth to Top: 4650' Bottom: 4650' T.D. 4675'
Ft Scott Depth to Top: 4433' Bottom: 4433' T.D. 4440'

API Number: 15 - 055-10,168 -00-00
Lease Name: Graves Vance (Pinex)
Well Number: #1
Spot Location (QQQQ): _____ - SW - SW - SW
330' Feet from North / South Section Line
330' Feet from East / West Section Line
Sec. 9 Twp. 22 S. R. 33 East West
County: Finney
Date Well Completed: 1/6/62
Plugging Commenced: 6/20/08
Plugging Completed: 6/20/08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		418'	surface	8-5/8"	418'	none
		4821'	production	5-1/2"	4821'	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP in 5-1/2" w/ 2 sks cmt @ 4350' - Set 2ND CIBP w/ 2 sks cmt @ 1150' - Test csg to 300# - perforate 4 holes @ 1100' - Allied pumped 210 sks 60-40 poz w/ 4% gel @ 1200# down 5-1/2" Csg - shut in holding @ 450# - blow on 8-5/8" annulus - pumped 25 sks 60-40 w/ 4% gel down 8-5/8" x 5-1/2" csg annulus @ 200# - shut in @ 200# - holding

Name of Plugging Contractor: Allied cement Co. & Hartman Oil Co., Inc. License #: 30535 99996
Address: 12950 E 13th St N - Wichita, Ks. 67230-1457

Name of Party Responsible for Plugging Fees: Hartman Oil Co., Inc.
State of Kansas County, Finney, ss.

S T Mitchell (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) S.T. Mitchell

(Address) 4550 W 9 Mi Rd Garden City, KS 67846



and SWORN TO before me this 1st day of July, 2008

Mary L. Riffel My Commission Expires: 1-13-2010
Notary Public

PK