

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Vincent Oil Corporation  
Address: 155 N. Market, Sute 700  
Phone: (316) 262-3573 Operator License #: 5004  
Type of Well: Dry and Abandoned Docket #: \_\_\_\_\_  
*(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other)* *(If SWD or ENHR)*  
The plugging proposal was approved on: 5/5/2008 (Date)  
by: Greg Eves (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
None Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. 4236  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 095-22146-00-00  
Lease Name: Sparks  
Well Number: 1-14  
Spot Location (QQQQ): ~ W/2 - NE - NW - SE  
2310 Feet from  North /  South Section Line  
1935 Feet from  East /  West Section Line  
Sec. 14 Twp. 28 S. R. 7  East  West  
County: Kingman  
Date Well Completed: 5/10/2008  
Plugging Commenced: 5/11/2008  
Plugging Completed: 5/11/2008

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		0	259	8 5/8"	259'	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Wellbore full of drilling mud, spotted cement plugs through drill pipe as follows: 35 sx @ 1150', 35 sx @ 700', 35Sx @ 309' and 25 sx @ 60'; cement circulated to surface; plugged rathole with 15 sx. , used 60 / 40 poz with 4% gel for all plugs. plugging completed @ 5:00 pm 5/11/2008. Allied Cement Ticket # 31078

Name of Plugging Contractor: Pickrell Drilling Company Inc. License #: 5123

Address: P.O. Box 1303, Great Bend, Kansas 67530-1303

Name of Party Responsible for Plugging Fees: Vincent Oil Corporation

State of Kansas County, Sedgwick, ss.

M.L. Korpage


(Employee of Operator) or (Operator) on above-described well, duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is true and correct, and the same are true and correct, so help me God.

(Signature)

(Address) 155 N Market, Suite 700, Wichita, Kansas 67202

SUBSCRIBED and SWORN TO before me this 1 st. day of July, 20 08

Yolanda Eubanks My Commission Expires: \_\_\_\_\_  
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
KANSAS CORPORATION COMMISSION

JUL 03 2008

PIA

# ALLIED CEMENTING CO., LLC. 31078

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:  
*Medicine Lodge, KS.*

**SPARKS**

DATE <i>5-11-08</i>	SEC <i>14</i>	TWP. <i>26S</i>	RANGE <i>7W</i>	CALLED OUT <i>11:00 AM</i>	ON LOCATION <i>2:00 PM</i>	JOB START <i>3:30 PM</i>	JOB FINISH <i>5:00 PM</i>
LEASE	WELL# <i>1-14</i>	LOCATION <i>Kingman, KS, 54+14 Sec, 1S</i>			COUNTY <i>Kingman</i>	STATE <i>KS</i>	
OLD OR NEW (Circle one)		<i>to 10<sup>th</sup> Ave, 3E, 2S, 1/2 E, N1/2 to</i>					

CONTRACTOR <i>Pickrell #1</i>	OWNER <i>Vircent oil Co.</i>
TYPE OF JOB <i>Rotary Pkg</i>	
HOLE SIZE <i>7 7/8</i>	T.D. <i>1150'</i>
CASING SIZE <i>8 7/8</i>	DEPTH <i>259'</i>
TUBING SIZE	DEPTH
DRILL PIPE	DEPTH
TOOL	DEPTH
PRES. MAX <i>350</i>	MINIMUM <i>100</i>
MEAS. LINE	SHOE JOINT
CEMENT LEFT IN CSG. <i>See Remarks</i>	
PERFS.	
DISPLACEMENT <i>See Remarks</i>	

EQUIPMENT			
PUMP TRUCK # <i>352</i>	CEMENTER <i>Thomas Demerlow</i>		
	HELPER <i>Greg G.</i>		
BULK TRUCK # <i>389</i>	DRIVER <i>Randy F.</i>		
BULK TRUCK #	DRIVER <i>David F.</i>		
COMMON <i>87 A</i>	@ <i>14.20</i>	<i>1235.40</i>	
POZMIX <i>58</i>	@ <i>7.20</i>	<i>417.60</i>	
GEL <i>5</i>	@ <i>18.75</i>	<i>93.75</i>	
CHLORIDE	@		
ASC	@		
	@		
	@		
	@		
	@		
	@		
	@		
HANDLING <i>150</i>	@ <i>2.15</i>	<i>322.50</i>	
MILEAGE <i>35 x 150 x .09</i>		<i>472.50</i>	
		TOTAL	<i>2541.75</i>

REMARKS:

*File set @ 1150' Load hole Pump 8 1/2 Fresh ahead,  
35 sx 60:40:4, 3 bbl Fresh, 11 Bbl mud, Pipe  
set @ 700', Load hole Pump 8 1/2 Fresh, 35 sx  
60:40:4, 3 Bbl Fresh, 4 1/2 mud, Pipe set @  
309', Load hole Pump 10 Bbl Fresh ahead  
35 sx 60:40:4, 2 1/4 Bbl Fresh, Pipe set  
@ 60' Pump 25 sx 60:40:4, Cement airhead  
to surface, Plug bathole w/ 15sx  
Thank you*

SERVICE

DEPTH OF JOB <i>1150'</i>		
PUMP TRUCK CHARGE		<i>917.00</i>
EXTRA FOOTAGE	@	
MILEAGE <i>35</i>	@ <i>7.00</i>	<i>245.00</i>
MANIFOLD	@	
	@	
	@	
		TOTAL <i>1162.00</i>

CHARGE TO: *Vircent oil Co.*

STREET \_\_\_\_\_

CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

PLUG & FLOAT EQUIPMENT

<i>None</i>	@	
	@	
	@	
	@	
	@	
		TOTAL _____

To Allied Cementing Co., LLC.  
You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME *Mike Kern*

SIGNATURE *Mike Kern*

SALES TAX (If Any) \_\_\_\_\_

TOTAL CHARGES ~~\_\_\_\_\_~~

DISCOUNT ~~\_\_\_\_\_~~ IF PAID IN 30 DAYS

ANY APPLICABLE TAX  
WILL BE CHARGED  
UPON INVOICING

RECEIVED  
KANSAS CORPORATION COMMISSION  
JUL 03 2008  
CONSERVATION DIVISION  
WICHITA, KS