

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Woolsey Operating Company, LLC  
Address: 125 N. Market, Suite 1000, Wichita, KS 67202  
Phone: (316) 267-4379 x107 Operator License #: 33168  
Type of Well: D&A Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 02/19/2008 (Date)  
by: Dave Wertz (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
n/a Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 095-22130 0000  
Lease Name: MESSENGER A  
Well Number: 1  
Spot Location (QQQQ): NW - NE - NE - SW  
2515 Feet from  North /  South Section Line  
1990 Feet from  East /  West Section Line  
Sec. 8 Twp. 30 S. R. 6  East  West  
County: KINGMAN  
Date Well Completed: 2/18/2008  
Plugging Commenced: 2/19/2008  
Plugging Completed: 2/20/2008

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
n/a						

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

1st plug: 1150' w/ 35 sx cmt through drill pipe

2nd plug: 800' w/ 35 sx

3rd plug: 270' w/ 60 sx

4th plug: 60' w/ 25 sx Rat hole: w/ 15 sx

*KCC Pkt 201  
CP 213*

Name of Plugging Contractor: Hardt Drilling Co., Inc. LLC License #: 5020 33902  
Address: 10286 SW 170th Ave, Nashville, KS 67112

RECEIVED  
KANSAS CORPORATION COMMISSION


Name of Party Responsible for Plugging Fees: Woolsey Operating Company, LLC  
State of Kansas County, Sedgwick, ss.

JUL 17 2008

Dean Pattisson (Employee of Operator) or (Operator) on above-described well in Wichita, KS duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

CONSERVATION DIVISION

(Signature) \_\_\_\_\_  
(Address) 125 N. Market, Suite 1000, Wichita, KS 67202



and SWORN TO before me this 17th day of July, 20 08  
Debra K. Clingan My Commission Expires: March 27, 2010  
Debra K. Clingan, Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*[Handwritten initials]*

# ALLIED CEMENTING CO., LLC. 31309

Federal Tax I.D. XXXXXXXXXX

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:  
*Medicine Lodge, KS.*

KCC PPT  
Per operator

DATE <i>2-19-08</i>	SEC. <i>8</i>	TWP. <i>30s</i>	RANGE <i>06 W</i>	CALLED OUT <i>3:30 AM</i>	ON LOCATION <i>7:30 AM</i>	JOB START <i>8:15 AM</i>	JOB FINISH <i>10:00 AM</i>
LEASE <i>Messenger</i>		WELL # <i>A-4</i>	LOCATION <i>Rago, KS. 14+42 Jct Kingman</i>		COUNTY <i>Kingman</i>	STATE <i>Kansas</i>	
OLD OR NEW (Circle one) <i>A-1</i> <i>4 east 1/8 S, E/S</i>							

CONTRACTOR *Hardt Rig #1*

TYPE OF JOB *Rotary Plug*

HOLE SIZE *7 7/8"* T.D. \_\_\_\_\_

CASING SIZE *8 5/8"* DEPTH *219'*

TUBING SIZE \_\_\_\_\_ DEPTH \_\_\_\_\_

DRILL PIPE *4 1/2"* DEPTH *1150'*

TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_

PRES. MAX *200* MINIMUM \_\_\_\_\_

MEAS. LINE \_\_\_\_\_ SHOE JOINT \_\_\_\_\_

CEMENT LEFT IN CSG. \_\_\_\_\_

PERFS. \_\_\_\_\_

DISPLACEMENT *Mud/Fresh*

EQUIPMENT

PUMP TRUCK CEMENTER *Carl Balding*

# *1343* HELPER *Steve Kramer*

BULK TRUCK

# *389* DRIVER *Heath McMurray*

BULK TRUCK

# \_\_\_\_\_ DRIVER \_\_\_\_\_

OWNER *Woolsey Operating Co.*

CEMENT

AMOUNT ORDERED *145 sx 60:40:4%6el*

COMMON	<i>87 A</i>	@	<i>14.20</i>	<i>1235.40</i>
POZMIX	<i>58</i>	@	<i>7.20</i>	<i>417.60</i>
GEL	<i>5</i>	@	<i>18.75</i>	<i>93.75</i>
CHLORIDE		@		
ASC		@		
		@		
		@		
		@		
		@		
		@		
		@		
		@		
		@		
HANDLING	<i>150</i>	@	<i>2.15</i>	<i>322.50</i>
MILEAGE	<i>50 x 150 x .09</i>			<i>675.00</i>
				TOTAL <i>2744.25</i>

REMARKS:

*Pump 35 sx - 1150'*

*35 sx - 800'*

*35 sx - 270'*

*25 sx - 60'*

*15 sx - lat hole*

SERVICE

DEPTH OF JOB *1150'*

PUMP TRUCK CHARGE *912.00*

EXTRA FOOTAGE @ \_\_\_\_\_

MILEAGE *50* @ *7.00* *350.00*

MANIFOLD @ \_\_\_\_\_

@ \_\_\_\_\_

@ \_\_\_\_\_

CHARGE TO: *Woolsey Operating*

STREET \_\_\_\_\_

CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

TOTAL *1267.00*

PLUG & FLOAT EQUIPMENT RECEIVED  
KANSAS CORPORATION COMMISSION

JUL 18 2008

CONSERVATION DIVISION  
WICHITA, KS

To Allied Cementing Co., LLC.  
You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME *Mark E Stamps*

SIGNATURE *MARK E STAMPS*

SALES TAX (If Any) \_\_\_\_\_

TOTAL CHARGES *[scribble]*

DISCOUNT *[scribble]* IF PAID IN 30 DAYS

ANY APPLICABLE TAX  
WILL BE CHARGED  
UPON INVOICING