

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Te-Pe Oil & Gas
 Address: PO Box 522, Canton, KS 67428
 Phone: (620) 628-4428 Operator License #: 5920
 Type of Well: oil Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: _____ (Date)
 by: Jeff Klock (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
Simpson Depth to Top: 3232 Bottom: 3288 T.D. _____
Viola Depth to Top: 3130 Bottom: 3232 T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-115-20,819-00-00
 Lease Name: W. Scully *KCC PKT per CP 2/3*
 Well Number: 1-10
 Spot Location (QQQQ): 230'E - NE - NE - SE/4
2310 Feet from North / South Section Line
100 Feet from East / West Section Line
 Sec. 10 Twp. 18 S. R. 01 East West
 County: Marion
 Date Well Completed: _____
 Plugging Commenced: 6-30-08
 Plugging Completed: 7-2-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Simpson	Oil, Water	0	215	8-5/8	215	0
Viola	Oil, Water	0	3271	5-1/2	3271	1550

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Pulled rods, pulled tubing out, sanded off bottom, loaded hole with water, dug cellar, unpacked casing head, set floor, pulled slips, had 11" stretch, sand at 3050', bailed 5 sacks cement, ripped casing at 1550', pipe came free, pulled casing up to 265', pumped 120 sacks cement to surface, pulled rest of casing. Top hole with cement.

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925
 Address: 190 US Highway 56, Ellinwood, KS 67526
 Name of Party Responsible for Plugging Fees: TE-PE Oil & Gas
 State of Kansas County, McPherson, ss.

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 16 2008
CONSERVATION DIVISION
WICHITA, KS

Terry P. Bandy (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Terry Bandy
 (Address) P.O. Box 522, Canton, Kansas 67428

CYNTHIA G. BEBEKE
NOTARY PUBLIC
STATE OF KANSAS
My Appointment Expires 5-15-2010

SUBSCRIBED and SWORN TO before me this 15th day of July, 2008
Cynthia G. Bebeke My Commission Expires: May 15, 2010
 Notary Public