

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Midwestern Exploration Co.
Address: 3500 S. Boulevard, Suite 2B, Edmond, OK 73013
Phone: (405) 340-4300 Operator License #: 5263
Type of Well: Gas Docket #: --
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 6/25/08 (Date)
by: Jack MacLaskey (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Herrington Depth to Top: 2582' Bottom: 2598' T.D. _____
Krider Depth to Top: 2612' Bottom: 2632' T.D. _____
L. Krider Depth to Top: 2652' Bottom: 2688' T.D. 3150'

API Number: 15 - 175-21461 - 00-00
Lease Name: Chambers
Well Number: 2-15
Spot Location (QQQQ): SE NW SE/4 NW/4
1980 ³³¹⁷ Feet from North / South Section Line
1980 ³⁴⁴⁸ Feet from East / West Section Line
Sec. 15 Twp. 33 S. R. 32 East West
County: Seward
Date Well Completed: 6/15/95
Plugging Commenced: 6/26/08
Plugging Completed: 6/30/08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Herrington	Gas/Water	585	Surface	8 5/8"	585'	0
Krider	Gas/Water	3150'	Surface	4 1/2"	3150'	
L. Krider	Gas/Water					
Winfield	Water					

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

6-26-08 Displace wellbore w/45 bbls. 9.5# 40 vis mud w/pump and plug method.
6-27-08 Cut casing off at 1012' and pulled out of hole.
6-30-08 Circulated hole with 40 bbls. 9.5# 40 vis mud, pumped 50 sx cement from 1000' to 850'. Pumped 50 sx cement from 600' to 450', pumped 15 sx cement from 40' to surface, cut off and plated.


Name of Plugging Contractor: Jerry Dunkin, Inc. License #: 8733
Address: P. O. Box 389, Enid, Oklahoma 73702

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 14 2008

Name of Party Responsible for Plugging Fees: Midwestern Exploration Co.
State of Oklahoma County, Oklahoma, ss.
Dale J. Lollar, President

CONSERVATION DIVISION

(Employee of Operator) or (Operator) on above-described well, Dale J. Lollar sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) [Handwritten Signature]
(Address) 3500 S. Blvd, Ste. 2B, Edmond, OK 73013
SUBSCRIBED and SWORN TO before me this 10th day of July, 2008
Virginia Means My Commission Expires: 7/12/2009
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten initials]