

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, Kansas 67202

Well Plugging Record
K.A.R. -82-3-117

API NUMBER 15-135-23243 -00-00
LEASE NAME Dugan
WELL NUMBER A #2

TYPE OR PRINT

NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

1347 1320 Ft. from South Line of Section
2381 2410 Ft. from East Line of Section
KCC PRT PER CP213

LEASE OPERATOR American Energies Corporation SPOT LOCATION 100' W of W/2 W/2 SE SW1/4 SW1/4 SE
ADDRESS 155 N Market, Suite 710 Section 33 Township 16S Range 21W
CITY, STATE, ZIP Wichita, KS 67202 County Ness
PHONE # 316-263-5785 Date Well Completed 4/28/88
Character of Well SWD Date Plugging Commenced 7/11/08
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed 7/14/08

The plugging proposal was approved on 6/16/2008 (date)
by Steve Bond - KCC State Plugging Agent (KCC District Agent's Name)
Is ACO-1 Filed? Yes Previously If not, is well log attached? On file with KCC
Producing Formation(s) None Depth to Top Bottom T.D. 4430'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface	Water sands	268'	0'	8 5/8" 23#	268'	None
Production	Saltwater	0'	4400'	5 1/2"	4360'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

7/11/08 - Rigged up Cheyenne Well Service. Ran casing jars down to 4380'. Came out and TIH with 2 7/8" tubing to 4360'. SION

7/14/08 - Hooked up Allied Cementing. Mixed and ran 61 bbls gel down and then a 25 sx 60/40 poz plug down. Hooked up Allied Cement and mixed 160 sx and circulated cement to surface.

Pulled tubing out, hooked up surface pipe and pressured up to 500#. Topped casing off with 2 sx. Rigged down.

Name of Plugging Contractor Allied Cementing Cheyenne Well Service Inc
License No. 6454
Address P.O. Box 31 City: Russell State: Kansas Zip 67665

KCC PRT PER CP213

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: American Energies Corporation (Operator)


STATE OF KANSAS COUNTY OF Sedgwick, ss.

Alan L. DeGood, President (Employee of Operator or (Operator) of above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.

(Signature) Alan L. DeGood
(Alan L. DeGood, President, American Energies Corporation)

(Address) 155 North Market, Suite 710 City: Wichita State: Kansas Zip 67202

SUBSCRIBED AND SWORN TO me this 15th day of July 2008



Melinda S. Wooten, Notary Public

My Commission Expires: 3/12/12

Form CP-4
Revised 12-92

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 17 2008

CONSERVATION DIVISION
WICHITA, KS

Handwritten initials/signature

