

4- 090572

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API number: 15-179-21,097-0000

SE SW NW / 4 SEC. 13, 09 S, 28 W
2970 feet from S section line
4290 feet from E section line

10-14

Operator license# 30717
Operator: Downing-Nelson Oil Company
Address: P.O. Box 372
Hays, Kansas 67601

Lease: Herl Well # 1
County: Sheridan
Well total depth 4192 ^{136.24} feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 261 feet

Aband. oil well _____, Gas well _____, Input well _____, SWD _____, D & A X

Plugging contractor: Vonfeldt Drilling, Inc. License# 9431

Address: Russell, Kansas 67665

Company to plug at: Hour: _____ - Day: 11 Month: October Year: 1999

Plugging proposal received from: Bill Owen

Company: Vonfeldt Drilling, Inc. Phone: _____ -

Were: Order 200 sxs 60/40 pozmix - 6% gel.

Spot all plugs through drill pipe with heavy mud between all plugs.

Plugging Proposal Received by: Ed Schumacher

Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 7:00 A.M., Day: 14, Month: October, Year: 1999

Actual plugging report: _____

1st. Plug at 2400' w/25 sxs cement.

2nd. Plug at 1495' w/100 sxs cement.

3rd. Plug at 310' w/40 sxs cement.

4th. Plug at 40' w/10 sxs cement.

15 sxs in rathole.

10 sxs in mousehole.

Anhydrite 2397' - Arbuckle - No

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD _____ BAD _____ Anhy.plug: YES X NO _____

Bottom plug(in place): YES _____, CALC _____, NO _____ Dakota plug: YES X, NO _____

Plugged through TUBING _____, CASING _____ Elevation: 2770 GL

I did[] / did not[] observe the plugging.

INVOICED

DATE 10-26-99

60736

Ed Schumacher
(agent)

Form CP-2/3

RECEIVED
STATE CORPORATION COMMISSION

OCT 15 1999
10-15-1999
CONSERVATION DIVISION
Wichita, Kansas

2