

6 062053

API NUMBER 15- 179-20,950-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW, SEC. 14, T 9 S, R 28W
4620 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5005

Lease Name R Scherzenberg Well # 1

Operator: Sunburst Exploration Co. Inc.

County Sheridan 135.53

Name & Address 125 N. Ecmportia

Well Total Depth 4170 feet

Wichita, Ks. 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 284

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Emphasis Oil Operations License Number 8241

Address Russell, Ks. 67665

Company to plug at: Hour: 10:00PM Day: 2 Month: Jan Year: 19 90

Plugging proposal received from John Collins

(company name) Emphasis Oil Operations (phone)

were: Order 190 sks 60/40 poz 6% gel 3% cal cl 1 sk f.c. and 8 5/8" plug.
Spot with drill pipe with no less than 36 vis mud between all plugs with good circulation and no fluid loss.

Plugging Proposal Received by Gilbert G. Scheck (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10:00PM Day: 2 Month: Jan Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 2400' w/25 sks

2nd plug at 1500' w/100 sks 1 sk f.c.

3rd plug at 325' w/40 sks

4th plug at 40' w/10 sks

15 sks in rathole

RECEIVED
STATE CORPORATION COMMISSION
01-17-1990
JAN 17 1990

Remarks: B. J. Titan
(If additional description is necessary, use BACK of this report)
observe this plugging.

INVOICED

DATE 1-30-90

INV. NO. 27235

Signed Gilbert G. Scheck (TECHNICIAN)