

8-11-87

API NUMBER 15-179-20,902-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW NE SW, SEC. 15, T 9 S, R 28 (W)

2310 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 03448

Lease Name Kennedy Well # 1-15

Operator: Walter A. Ohmart Jr.

County Sheridan 136.50

Name & Address: 1580 Lincoln Street Ste. 1180

Well Total Depth 4200 feet

Denver, Co. 80203

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 276'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____ Abercrombie Drlg.

Plugging Contractor _____ Wichita, Kansas License Number _____

Address _____

Company to plug at: Hour: _____ PM Day: 11 Month: 8 Year: 19 87

Plugging proposal received from Bill Craig

(company name) _____ (phone) _____

were: 8 5/8 set at 276' w/200 sx circ. hole with no less than 36 vis. mud with no loss or gain of fluid.

Order 200 sx 60/40 poz 6% gel 3% c.c. 8 5/8 w.p.

Balance all plugs w/mud. use joint of pipe to circ. rat and mouseholes: B.J. Titan Cement Co.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All 1:45 PM Part 11 None X

Operations Completed: Hour: 1:45 PM Day: 11 Month: 8 Year: 19 87

ACTUAL PLUGGING REPORT

Spot drill pipe @ 2450' displace 25 sx cmt. blend

" " " 1500' displace 100 sx cmt. blend w/1 sx hulls

" " " 325' displace 40 sx cmt. blend --

" " " 40' displace 10 sx cmt. blend w/w.p.

15 sx rathole

Remarks: 10 sx mousehole Elev. 2812 K.B. Anhy. 4238-77
(If additional description is necessary, use BACK of this form.)

INVOICED

I (XXXX) did not observe this plugging.

DATE 9-3-87

Signed Carl Goodrow (TECHNICIAN)

INV. NO. 18006

Carl Goodrow