

4-060532

5-27

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-179-21,069-00-00

C NE NE /4 SEC. 27, 09 S, 28 W
4620 feet from S section line
660 feet from E section line

Operator license# 5422

Lease Leiker well # 1

Operator: Abercrombie Drilling, Inc.

County Sheridan

Address: 150 N. Main
Suite 801
Wichita, Kansas 67202

Well total depth 2397 feet ^{77.90}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 265 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Abercrombie RTD, Inc. License# 30684

Address: Wichita, Kansas 67202

Company to plug at: Hour: 12:30P.M Day: 27 Month: May Year: 94

Plugging proposal received from: Tony Martin

Company: Abercrombie RTD, Inc. Phone: 316-262-1841

Were: Order 190 sxs. 60/40 posmix - 6% gel with flocele.
Lost 751' of collars and drill pipe in hole. Attempted to fish but
couldn't recover any drill pipe. Space all plugs with heavy drilling
mud through drill pipe. Penetrated 8' of anhydrite.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 12:30P.M, Day: 27, Month: May, Year: 94

Actual plugging report:
1st. plug at 1600' w/125 sxs. - Dakota 1190'-1490'.
2nd. plug at 315' w/40 sxs. - Surface pipe to 265'.
3rd. plug at 40' w/10 sxs.
Rathole with 15 sxs. cement.
Skidded rig to Leiker A-1 location.

STATE RECEIVED
06-03-94
WICHITA, KANSAS
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD BAD Anhy. plug: YES NO X
Bottom plug(in place): YES , CALC , NO X Dakota plug: YES X, NO
Plugged through TUBING , CASING . Elevation: 2760 GL

I did [] / did not [X] observe the plugging.

Herb Deines
 (agent)

INVOICED
DATE 6-6-94
INV. NO. 40528
5-27