

6-3 4-031944

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-179-21,070-00-00

C E2 NE /4 SEC. 27, 09 S, 28 W
3960 feet from S section line
660 feet from E section line

Operator license# 5422 Lease Leiker well # A-1

Operator: Abercrombie Drilling, Inc. County Sheridan

Address: 150 N. Main Well total depth 4160 feet
Suite #801 Conductor Pipe: 0 inch @ 0 feet
Wichita, Kansas 67202 Surface pipe 13 3/8 Inch @ 245 feet

135.20

Aband. oil well ____, Gas well ____, Input well ____, SWD ____, D & A X

Plugging contractor: Abercrombie Rig #8 License# 5422

Address: Wichita, Kansas 67202

Company to plug at: Hour: A.M. Day: 3 Month: June Year: 94

Plugging proposal received from: Tony Martin

Company: Abercrombie Drilling, Inc. Phone: _____

Were: Order 190 sxs. 60/40 pozmix - 6% gel - 3% c.c.
Allied Cement Company.
Condition hole with 36 vis. mud.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 5:00A.M., Day: 3, Month: June, Year: 94

Actual plugging report:
Spot plugs with drill pipe.
1st. plug at 2400' w/25 sxs.
2nd. plug at 1450' w/100 sxs.
3rd. plug at 300' w/40 sxs.
4th. plug at 40' w/10 sxs. W.P.
Circulate 15 sxs. in rathole.

Remarks:
Condition of casing(in hole): GOOD ___ BAD ___ Any plug: YES X NO ___
Bottom plug(in place): YES ___, CALC ___, NO X Dakota plug: YES X, NO ___
Plugged through TUBING ___, CASING ___. Elevation: _____

I did [] / did not [X] observe the plugging.

Carl Goodrow

INVOICED
DATE 7-5-94
INV. NO. 40716

RECEIVED
STATE CORPORATION COMMISSION
JUN 30 1994
06-30-1994
CONSERVATION DIVISION
Wichita, Kansas
Form CP-27

HO