

6070271

API NUMBER 15-179-20, 782-100-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION SW-SW-SE, SEC. 3, T 9 S, R 29 01W
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5140

Operator: FRONTIER OIL CO.

Name & Address 1720 KANSAS STATE BANK

BLDG., WICHITA, KANS.

67202

330 feet from (S) section line

2310 feet from (E) section line

Lease Name REITZHECK Well # 1

County SHERIDAN

Well Total Depth 4190 ^{136.18} feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 246

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated TAG # 76

Plugging Contractor RED TIGER DRILLING License Number 5302

Address WICHITA, KANSAS 67202

Company to plug at: Hour: 3:00 PM Day: 6th Month: DEC Year: 19 84

Plugging proposal received from SAM WAGONER

(company name) RED TIGER DRILG. (phone) 316-263-1201

were: 8 5/8" - 246' 50' CUL #1/160^{SK} COMMON GEL - CA-CL - (BY ALLIED CRT)

ORDER 200^{SK} 50' FORMIX GEL - CA-CL - 1^{SK} 70' CELE AND 8 5/8" PLUG.

SPOT WITH DRILL STEM, TURN HOLE OVER, HEAVY MUD BETWEEN ALL PLUGS

LOWER SUCTION BEFORE TURNING HOLE OVER. (NO WERC 50' IN)

NO CIRCULATION PROBLEMS, ELEV. 2785' ANVH. 2405

Plugging Proposal Received by Marion J. Smith
DOK (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 6:00 PM Day: 6th Month: DEC Year: 19 84

ACTUAL PLUGGING REPORT ORDERED 200^{SK} 50' FORMIX GEL - CA-CL - 1^{SK} 70' CELE

AND 8 5/8" PLUG. - SPOTTED WITH DRILL STEM - TURNED HOLE OVER, HEAVY MUD BETWEEN

1st PLUG @ 2430' ELEV. #30^{SK} CRT, 2nd PLUG @ 1530' ELEV. #100^{SK} CRT.

1/2^{SK} 70' CELE MIXED IN, THIRD PLUG @ 270' ELEV. #50^{SK} CRT.

4th PLUG ^{SOLID BRIDGE} HULL'S - PLUG @ 40' ELEV. #0^{SK} / 10^{SK} CRT.

10^{SK} IN RAT HOLE @ (CIRCULATE) CEMENTED BY ALLIED CRT.

Remarks:

(If additional description is necessary, use BACK of this form.) DEC 17 1984

INVOLVED

DATE 1-3-85

INV. NO. 6272

Signed Marion J. Smith
BOIC (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas