

6 030559

API NUMBER 15-179-20,037-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

N 2 1/2 S. SEC. 3, T 9 S, R 22 W

990 feet from S section line

3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5267

Lease Name REITCHECK Well # 1

Operator: K & F PET. INC.

County SHERIDAN 136.50

Name & Address HARDAGE CENTER STB. 300

Well Total Depth 4200 feet

WICHITA, KANSAS

Conductor Pipe: Size \_\_\_\_\_ feet

67202

Surface Casing: Size 8 5/8 feet 301

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor ABERCROMBIE DRUG License Number 179

Address WICHITA, KANSAS 67202

Company to plug at: Hour: PM Day: 9 Month: 8 Year: 19 85

Plugging proposal received from HAROLD MALEY

(company name) ABERCROMBIE DRUG (phone) \_\_\_\_\_

were: 8 5/8 BIT @ 301 W/225 SX. WITH HOLE FULL OF MUD LESS THAN 36.

VIS. MUD AND NO LOSS OR GAIN OF FLUID. SPOT CEMENT PLUGS WITH

DRILL PIPE ORDER 190 SX. 60/40 P.D. 6262L 3" 8 5/8 W.P.

BJ TITAN CMT CO. WATER FROM CREEK HAULED

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 10:30 PM Day: 9 Month: 8 Year: 19 85

ACTUAL PLUGGING REPORT SPOT D.P @ 2450' BREAK CIRC. DISPLACE 25 SX.

CMT. MIX LAY DOWN D.P. TO 1500' DISPLACE 100 SX. CMT MIX + 1 SX. HULLS

LAY DOWN D.P. TO 350' DISPLACE 40 SX. CMT. MIX LAY DOWN D.P.

PUSH W.P. TO KELLY DEPTH DUMP 1 SX HULLS FILL HOLE TO

BASE OF CELLAR W/10 SX. CMT MIX. DISPLACE 15 SX. IN RATHOLE/W/Joint

OF PIPE PLUG COMPLETE

Remarks: ELEV. 2817 ANHY 2441-75

(if additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED

DATE SEP 17 1985

SEP 16 1985

Signed Carl Goodrow  
(TECHNICIAN)

INV. NO. 10094

09-16-1985

CONSERVATION DIVISION  
Wichita, Kansas

FORM CP-2/3  
Rev. 01-84

25  
9-13-85  
MPS