

4-031667

3-11

206
R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-179-20,468-00-00
NW NW /4 SEC. 27, 09 S, 29 W
4620 feet from S section line
4620 feet from E section line

Operator license# 4767 Lease Clark well # P-1

Operator: Ritchie Exploration, Inc. County Sheridan

Address: 125 N. Market Well total depth 4292 feet
Suite 1000 Conductor Pipe: 0 inch @ 0 feet
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 266 feet

139.49

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Kelso Casing Pulling License# 6050

Address: Chase, Kansas

Company to plug at: Hour: P.M. Day: 11 Month: March Year: 92

Plugging proposal received from: David

Company: Kelso Casing Pulling Phone:

Were: Order sand and common cement. Strip pipe.
Order 250 sx. 65/35 pozmix - 10% gel. - 500# hulls - Allied Cement Co.
Hole open to PSTD by bailer.

RECEIVED
STATE CORPORATION COMMISSION

APR 05 1992
04-03-1992

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[X], Part[None]
Wichita, Kansas

Completed: Hour: 4:00P.M., Day: 11, Month: March, Year: 92

Actual plugging report: 8 5/8" set @ 266' w/220 sx. 4 1/2" set @ 4283'
w/200 sx. Perf's 3980' - 4233'. PSTD 3870'. One shot recovered 1500'
Shot @ 2100' anhy. Mix and pump down 4 1/2" to 2100'. Lay down 4 1/2"
casing, squeeze 4 1/2" with total of 250 sx. cement blend with 500#
hulls mixed in to. Max P.S.I. 500#. Close in P.S.I. 150#. Plug
complete.

Remarks:
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING . Elevation: GL

I did[X] / did not[] observe the plugging. Carl Goodrow

INVOICED
DATE 4-8-92
BY 34913

(agent)