

3-13

207
R

4- 031668

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-179-20,490-00-00
NE SE /4 SEC. 28, 09 S, 29 W
1980 feet from S section line
660 feet from E section line

Operator license# 4767 Lease Pratt well # B-P1

Operator: Ritchie Exploration, Inc. County Sheridan

Address: 125 N. Market Well total depth 4250 feet
Suite 1000 Conductor Pipe: 0 inch @ 0 feet
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 253 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Kelso Casing Pulling License# 6050

Address: Chase, Kansas

Company to plug at: Hour: P.M. Day: 13 Month: March Year: 92

Plugging proposal received from: Dave

Company: Kelso Casing Pulling Phone:

Were: Order sand and common cement - Strip pipe.
Order 250 sx. 65/35 pozmix - 10% gel. - 500# hulls - Allied Cement Co.
Hole open to PSTD by bailer.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 12:45P.M., Day: 13, Month: March, Year: 92

Actual plugging report: 8 5/8" set @ 253' w/220 sx. 5 1/2" set @ 4251'
w/200 sx. Perf's 3970' - 4016'. T.O.C. 2200'. Sand back to 3920'
with 5 sx. common cement on sand with bailer to 3880'. Recovered 1400'
of 5 1/2" with shots @ 2100' - 1600' - 1400'. Mix and pump cement blend
thru 5 1/2" casing to 2100'. Lay down 5 1/2" casing. Squeeze 8 5/8"
casing with total 250 sxs. cement blend w/500# hulls mixed into
P.S.I. 500#. Close in P.S.I. 200#. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
WICHITA, KANSAS
04-09-1992

Remarks:
Condition of casing(in hole): GOOD X BAD Any plug: YES X NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING . Elevation: GL

I did X / did not observe the plugging. Carl Goodrow

DATE 4-8-92

INV. NO. 34914

(agent)
Form CP-2/3