

6 070875

11-20

API NUMBER 15- 193-20,532-00-00

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW SE NW, SEC. 7, T 9 S, R 32 W/E
2970 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6113

Lease Name Horn Well # 1-7

Operator: Landmark Oil Explor Inc.

County Thomas

Name & Address 250 N. Water #308

Well Total Depth 4770 155.02 feet

Wichita, Ks. 67202

Conductor Pipe: Size 0 feet

Jeff R. Wood

Surface Casing: Size 5/8 feet 303

Abandoned Oil Well Gas Well Input Well SWD Well D&A xx

Other well as hereinafter indicated

Plugging Contractor Murfin Drilling Co. License Number 6033

Address Wichita, Ks.

Company to plug at: Hour: Am Day: 20 Month: Nov Year: 19 90

Plugging proposal received from Rodney Farr

(company name) Murfin Drilling Inc. (phone)

were: 8 5/8 303 ft. s.p. cwc w/195 sks 60/40 poz 2% gel 3% cal cl by Halco.

Elv. 3109 Anhy 2696. Miss well, No cir problems. Mud condition 45 vis. 9.2 weight.

10 water loss. Proposal 200 sks 60/40 poz 6% gel 3% cal cl w/l f.c. Spot with drill stem, circ heavy mud between plugs. 25 sks at 2700 ft. 100 sks w/l f.c. at 1860 -

40 sks at 350 - 10 sks at 40 -15 sks rathole - 10 sks in mousehole. Circ.

Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None xx

Operations Completed: Hour: 6:00 PM Day: 20 Month: Nov Year: 19 90

ACTUAL PLUGGING REPORT Murfin Drilling ordered 200 sks 60/40 poz 6% gel 3% ca cl.

1 sk f.c. Spotted with drill stem, heavy mud between all plugs.

1st 25 sks at 2700 ft. 15 sks in rathole circulate RECEIVED

2nd plug 100 sks at 1860 w/l sk f.c. 10 sks in mousehole (circulate by Halco)

3rd plug 40 sks at 350.

4th plug 10 sks at 40.

DEC 6 1990
12-06-1990
CONSERVATION DIVISION
Wichita, Kansas

Remarks: (If additional description is necessary, use BACK of this form.)

I (did not) observe this plugging.

DATE 12-10-90

Signed Marion J. Schmidt (TECHNICIAN)

INV. NO. 30202