

6 070821

1-2

120

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 193-20,011 400-01

SW SE, SEC. 16, T 9 S, R 32 (W/E)

660 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3295

Lease Name Keller Well # owwo 1-16

Operator: David W. Clothier

County Thomas 154.05

Name & Address: 225 N. Market #333

Well Total Depth 4740 feet

Address: Wichita, Ks. 67202

Conductor Pipe: Size 0 feet

David W. Clothier

Surface Casing: Size 8 5/8 feet 278

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A ^x

Other well as hereinafter indicated was owwo

Plugging Contractor Murfin Drilling License Number Tag 601 6033

Address 250 N Water #300, Wichita, Ks. 67202

Company to plug at: Hour: AM Day: 2nd Month: Jan. Year: 19 90

Plugging proposal received from Steve Carlton

(company name) Murfin Drilling (phone)

were: 8 5/8" 278' cwc w/200 sks cement by Halliburton. Miss well. Elev. 3062'. Anhy 2650', No circulation problems. Mud condition 49 vis. 9.8 weight. 11 water loss. Proposal 205 sks 60/40 poz 6% gel 3% cal cl and 8 5/8" plug. 30 sks at 2670' 100 sks w/1 sk f.c. at 1800'. 50 sks cement at 330'. 10 sks cement w/ w.p. at 40'. 15 sks in rathole, Circulate.

Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None ^x

Operations Completed: Hour: 5:30AM Day: 2nd Month: Jan Year: 19 90

ACTUAL PLUGGING REPORT Murfin ordered 205 sks 60/40 poz 6% gel 3% cal cl and 8 5/8" plug. Spot with drill stem (circulate) heavy mud between all plugs.

1st plug at 2670' w/30 sks cement. 4th plug at 40' w/w.p. and 10 sks cement.

2nd plug at 1800' w/100 sks cement w/ 1 sk f.c. 15 sks in rathole (circulate)

3rd plug at 330' w/50 sks cement.

Remarks: (If additional description is necessary, use BACK of this form) RECEIVED STATE CORPORATION COMMISSION 01-17-1990 JAN 17 1990

I (did / did not) observe this plugging.

INVOICED

Signed Marion J. Schmidt (TECHNICIAN)

DATE JAN 26 1990

INV. NO. 27185 1-2 FEB 28 1990