

4 060068

3-7

113 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 193-20,504-00-00

SW SE NW, SEC. 17, T 9 S, R 32 W EX

2970 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3372

Lease Name Steinle Well # 1

Operator: Morrison-Dixon Oil Operations, Inc.
Name &

County Thomas 152.75

Address 100 N. Main, Suite 801

Well Total Depth 4700 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 257

Abandoned Oil Well Gas Well Input Well SWD Well D&A XXXXXX

Other well as hereinafter indicated

Plugging Contractor Blue Goose Drilling Co License Number 5104

Address Great Bend, KS

Company to plug at: Hour: 3:00PM Day: 7 Month: March Year: 19 90

Plugging proposal received from Martin Miller

(company name) Blue Goose Drilling Co. (phone) 316-792-5633

were: Order 190 sxs, 60/40 pos 6% gel 1/2 floccel per sx.

Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by Herb Deines

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None XXXXXXXXXXXXX

Operations Completed: Hour: 3:00PM Day: 7 Month: March Year: 1990

ACTUAL PLUGGING REPORT 1st plug at 2640' with 25 sxs. Anhydrite 2622-2654'

2nd plug at 1815' with 100 sxs. Dakota 1512-1812'

3rd plug at 310' with 40 sxs. Surface pipe to 257'

4th plug at 40' with 10 sxs. wiper plug at 40'

rathole with 15 sxs

Remarks: Allied Cementing

MAR 26 1990
03-26-1990

(If additional descriptions necessary, use BACK of this form.)

Wichita, Kansas

INVOICED

(did not) observe this plugging.

DATE 3-28-90

Signed  (TECHNICIAN)

INV. NO. 27746

Herb Deines