

To: 6 020443
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT
Operator License # 5123 and 4277

Operator: Pickrell and Bruce Anderson
Name &
Address 110 N. Market Suite 205
Wichita, Kansas 67202

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Pickrell Drilling License Number 5123

Address Wichita

Company to plug at: Hour: PM Day: 30 Month: Dec Year: 19 87

Plugging proposal received from Gary Christopher

(company name) Order 190 sks 60/40 Poz 6% Gel 3% Cal Cl 1 sk Flocal and 8 5/8" plug.
Pickrell Co. (phone) _____

were: Spot with drill pipe with no less than 36 vis. mud between all plugs
with good circulation and no fluid loss.

Plugging Proposal Received by Gilbert Balthazor
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 5:45PM Day: 31 Month: Dec Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 2630' w/25 sks
2nd plug at 1800' w/100 sks F.C.
3rd plug at 320' w/40 sks
4th plug at 40' w/10 sks wiper/
15 sks in rat hole.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

I (company) did not observe this plugging.

INVOICED

DATE 1-26-88

INV. NO. 19675

12-31-87
API NUMBER 15- 193-20,459-60-60
SE NE SE SEC. 18, T 9 S, R 32 W/E
1900 feet from S section line
540 feet from E section line
Lease Name Steinle Well # 1-B
County Thomas 153.56
Well Total Depth 4725 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 315

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas
JAN 25 1988
01-25-1988

Signed Gilbert Balthazor
(TECHNICIAN)
Gilbert Balthazor