

To: 6 100402
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

12-12
API NUMBER 15- 193-20,496-240
00-00
SE. NE. NE., SEC. 20, T. 9 S., R. 32 (W) EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

Operator: Red Oak Energy Inc.
Name & Address 111 West Douglas
Suite 507
Wichita, Ks. 67202

4290 feet from S section line
330 feet from E section line

Lease Name Sieinle Well # 1-20

County Thomas 155.35

Well Total Depth 4780 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 312

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A XX

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Company License Number 6033

Address Wichita, Ks.

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 _____

Plugging proposal received from Don Merchan

(company name) Murfin Drilling Company (phone) _____

were: Spot plugs through drill pipe w/heavy mud between all plugs.

1st plug at 2660' w/25 sks

2nd plug at 1835' w/100 sks Rathole 15 sks

3rd plug at 360' w/40 sks Mousehole

4th plug at 40' w/wiper plug and 10 sks

Plugging Proposal Received by David K. Wann
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None XX

Operations Completed: Hour: 3:30AM Day: 12 Month: Dec Year: 19 89

ACTUAL PLUGGING REPORT Hole reported plugged as above.
Order 190 sks 60/40 pozmix w/6% gel and 2 sks celoffaké or flocele.

Elevation: 3085 GL, Anhdrite depth: 2657 - 2687'

Remarks: Did not penetrate Arbuckle. Cemented by B. J. Titan.
(if additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION
JAN 17 1990
01-17-1990
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE JAN 26 1990
INV. NO. 27153

J.B.S.

Signed David Wann
(TECHNICIAN)