

6-2

4-020009

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-193-20610-00-00
NE NE NW /4 SEC. 21, 09 S, 32 W
330 feet from S section line
2970 feet from E section line

Operator license# 4629
Operator: Brito Oil Company, Inc.
Address: 200 E. First, Suite 208
Wichita, Kansas 67202

Lease: Renner Well # B-1
County: Thomas
Well total depth 4720 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8% Inch @ 294 feet

153.40

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Abercrombie RTD, Inc. License# 30684

Address: 150 N. Main St., Suite 801, Wichita, Kansas 67202

Company to plug at: Hour: _____ Day: 2 Month: June Year: 1993

Plugging proposal received from: Bill Craig

Company: Abercrombie RTD, Inc. Phone: 316-262-1841

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 2675 feet with	25	sacks	Rat hole:	15	sacks
2nd plug @ 1830 feet with	100	sacks			
3rd plug @ 345 feet with	40	sacks			
4th plug @ 40 feet with	10	sacks			

Plugging Proposal Received by: Ken Kuhn
Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 13:00, Day: 2, Month: June, Year: 1993

Actual plugging report: Hole reported plugged as above.
Order 190 sx 60/40 pozmix w/ 6% gel and 1.9 sx celloflake or flowcel.

Remarks: Allied Cementing performed the cementing.
Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: 3079 GL

I did[] / did not[] observe the plugging.

Ken Kuhn
(agent)
AKK

INVOICED

DATE 6-18-93
INV. NO. 37956

RECEIVED
Form CP-2/3
STATE CORPORATION COMMISSION

JUN 9 1993
06-09-1993
CONSERVATION DIVISION
Wichita, Kansas