

15-065-03220-00-00 3-26

6 031520

NOB

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 151956
NE SW NE, SEC. 29, T 10 S, R 23 W/Ex
3630 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30241
Operator: Geneva Resources Inc.
Name & Address: 50 California Suite #930
San Francisco, Ca 94111

Lease Name Diebolt LKC UnWell # 10-6
County Graham 127.20
Well Total Depth 3914 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 201

Abandoned Oil Well Gas Well Input Well X SWD Well D&A
Other well as hereinafter indicated E - 9110

Plugging Contractor Halliburton Services License Number
Address Hays, Ks.

Company to plug at: Hour: Pm Day: 26 Month: Mar Year: 19 91

Plugging proposal received from Gerald
(company name) Geneva (phone)

were: 8 5/8 set at 201 w/150 sks cwc. 5 1/2 set at 3890 w/150 sks. PBDT 3858.

Perf 3834 - 55. Order 350 sks 65/35 poz 10% gel 500 lbs. hulls.

Halliburton Cement Co Wellbrock Water Trucks. Pulled full string of tubing out of hole. Hole open. Shot holes at 1100 and 1925.

RECEIVED

APR 10 1991

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)
CONSERVATION DIVISION
Wichita, Kansas

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 3:10PM Day: 26 Month: Mar Year: 19 91

ACTUAL PLUGGING REPORT Sq 5 1/2 casing w/275 sks cement blend w/500 lbs.

hulls mixed in last 100 sks to max psi 800 lbs. Close in psi 350 lbs.

Sq 8 5/8 w/75 sks cement blend to max psi 350 lbs. Close in psi 150 lbs. Plug complete.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

(did / did not observe this plugging.)

DATE 4-17-91

INV. NO. 31557

Signed Carl Goodrow (TECHNICIAN)
Carl Goodrow

Gib S.