

9-27 15-065-22647-00-00

64
R

6-100440

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-22,647-00-00

SW SE NE /4 SEC. 34, 10 S, 23 W
2970 feet from S section line
990 feet from E section line

Operator license# 05135

Lease Klenk "B" well # 1

Operator: John O. Farmer, Inc.

County Graham 124.47

Address: P.O. Box 352
Russell, Kansas 67665

Well total depth 3830 feet
Conductor Pipe: inch @ feet
Surface pipe 8 5/8 Inch @ 216 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Emphasis Oil Operations License# 08241

Address: Russell, Kansas 67665

Company to plug at: Hour: ?? Day: Month: Year:

Plugging proposal received from: Larry Langhoffer

Company: Emphasis Oil Operations phone:

Were: **Spot plugs through drill pipe w/ heavy mud between all plugs.**

1st plug @ 1825 feet with 25 sacks Rat hole: 15 sacks

2nd plug @ 1040 feet " 100 " Mousehole: sacks

3rd plug @ 360 feet " 40 "

4th plug @ 40 feet " wiper plug & 10 sx

RECEIVED
STATE CORPORATION

NOV 12 1991

Plugging Proposal Received by: David K. Wann

Plugging operations attended by agent? All[], Part[Wichita, None]

Completed: Hour: 11:00am, Day: 27, Month: September, Year: 1991

Actual plugging report: Hole reported plugged as above.

Order 190 sx 60/40 pozmix w/ 6% gel and 2 sx celloflake or flowcel.

Remarks: Elevation: 2319 GL, Anhydrite depth: 1822 - 1868 feet

Did NOT penetrate Arbuckle, cemented by Allied

I did not observe the plugging.

David K. Wann
David K. Wann P.I.R.T. II
(agent)

INVOICED
DATE 11-25-91
INV. NO. 33850

Gib. S.