

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 30241

Operator: Geneva Resources Inc.  
Name & Address 50 California Street #930  
San Francisco, CA 94111

API NUMBER 13- 1955  
SW SE NE, SEC. 29, T 10 S, R 23 W/EX  
2970 feet from S section line  
990 feet from E section line  
Lease Name Diebolt LKC Unit 10-4  
County Graham 128.05  
Well Total Depth 3940 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 210

Abandoned Oil Well Gas Well Input Well x SWD Well D&A

Other well as hereinafter indicated E-9110

Plugging Contractor Halliburton Services License Number

Address Hays, Ks.

Company to plug at: Hour: AM Day: 26 Month: Mar Year: 19 91

Plugging proposal received from Gerald

(company name) Geneva (phone)

were: 8 5/8 set at 210 w/150 sks cwc. 5 1/2 set at 3967 w/800 sks cwc.

PBTD 3906. Perf 3820 - 24. Order 350 sks 65/35 poz 10% gel.

500 lbs. hulls. Halliburton Cement Co.

Wellbrock Water Trucks.

Pulled full string of tubing out of hole. Hole open and low fluid

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part x None

Operations Completed: Hour: 10:00AM Day: 26 Month: Mar Year: 19 91

ACTUAL PLUGGING REPORT Sq 5 1/2 casing w/335 sks cement blend w/500 lbs.

hulls mixed in last 135 sks cement to max psi 1000 lbs. Close in psi

1000 lbs. Sq 8 5/8 w/15 sks cement blend to max psi 250 lbs. Close in psi 250 lbs.

cement near surface. Plug complete.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-17-91

INV. NO. 31559

Signed Carl Goodrow  
(TECHNICIAN)  
Carl Goodrow