

6 031518

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- _____ 1955

NE SE NW SEC. 29, T 10 S, R 23 W/E
3630 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30241

Lease Name Diebolt LKC UNIT Well # 10-3

Operator: Geneva Resources Inc.

County Graham 128.37

Name & Address 50 California Suite #930

Well Total Depth 3950 feet

San Francisco, CA 94111

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 209

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated E 9110 KCC app.

Plugging Contractor Halliburton Services License Number _____

Address Hays, Ks.

Company to plug at: Hour: PM Day: 26 Month: Mar Year: 19 91

Plugging proposal received from Gerald

(company name) Geneva (phone) _____

were: 8 5/8 set at 209 w/150 sks cwc. 5 1/2 set at 3943 w/150 sks. PBTDF 3838

Perf 3696 - 3827. Order 450 sks. 65/35 poz 10% gel 500 lbs. hulls. Halliburton

Cement Co. Wellborck Water Trucks. Pulled full string of tubing out of hole. Hole

open. Low fluid level. Perf shots 1100 and 1925.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 6:50PM Day: 26 Month: Mar Year: 19 91

ACTUAL PLUGGING REPORT Sq 5 1/2 casing w/375 sks cement blend w/700 lbs.

hulls mixed into max psi 800 lbs. Close in 800 lbs. Sq 8 5/8 w/75 sks cement blend

to max psi 300 lbs. Close in 150 lbs. Plug complete.

RECEIVED STATE CORPORATION COMMISSION

APR 04 1991

Remarks: (If additional description is necessary, use BACK of this form.) Conservation Division Wichita, Kansas

INVOICED

DATE 4-11-91

INV. NO. 31485

3-26

J.S.

Signed Carl Goodrow (TECHNICIAN) Carl Goodrow