

6010176

CP 2/3

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-065-22021-00-00

SW, SEC. 26, T 10 S, R 23 W
1670 feet from N/W section line of SE cor.
4420 feet from W/B section line of SE cor.

TECHNICIAN'S PLUGGING REPORT

Operator License # 5420
Operator: White & Ellis
Name & Address: 5523 W. 10th
Great Bend Ks.

Lease Name Klenk Well # 1
County Graham
Well Total Depth 3840 124.80 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 266

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well (D&A)

Other well as hereinafter indicated _____

Plugging Contractor White & Ellis License Number 5420
Address Same

Company to plug at: Hour: PM Day: 6 Month: 8 Year: 19 84

Plugging proposal received from Judy Stieben
(company name) White & Ellis (phone) 376 792-2424

were: order 185 sx. cement 50/50 port mix 6% gel. 3% c.c.

1. sx hulls 1. 8 5/8 plug 1. SX. Flow Seal

Heavy mud between all plugs.

Pump cement down drill pipe.

Elev. 2286 Anhydrite 1816-54 Arbyuckle No

Dakota 1600 Plugging Proposal Received by Dale F. Balthazor (TECHNICIAN)
686-990

Plugging Operations attended by Agent?: All _____ Part _____ None (circled)

Operations Completed: Hour: 2:30 AM Day: 7 Month: 8 Year: 19 84

ACTUAL PLUGGING REPORT circulated @ 1830 for 20 mi.

25 SX. @ 1830

100 SX. @ 990 mixed with 1.5x. flow seal.

40 SX. @ 280 dumped 1.5x. hulls pushed plug to 40'

10 SX. @ 40

10 SX. in Rat Hole

Remarks: cementing to Allied (If additional description is necessary, use BACK of this form.)

RECEIVED STATE CORPORATION COMMISSION

AUG 13 1984

CONSERVATION DIVISION Wichita, Kansas

Signed Dale F. Balthazor (TECHNICIAN) 8-10-84 2

INVOICED (circled) Observe this plugging.

DATE 8-17-84

INV. NO. 3247

FORM CP-2/3 Rev. 01-84

8-7