

15-065-21866 00-00

6 031392

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-
SW NWSW, SEC. 36, T 10 S, R 23 WXX

1650 feet from 5 section line
~~3630~~ 230 feet from 6 section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5068

Lease Name McCall Well # 1

Operator: Black Petroleum Co.

County Graham

Name: Address Box 12922

Well Total Depth 4000 feet

Address Wichita, Ks. 67277

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 251

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Kansas

Company to plug at: Hour: Day: 17 Month: July Year: 19 90

Plugging proposal received from Vernon

(company name) Kelso (phone)

were: 8 5/8 set at 251 w/175 sks cwc 4 1/2 set at 3868 w/100 sks. PBtd 3828

w/100 sks. PBD 3828. T.O.C. 3300. Perf 3726 - 30. Order sand and common cement.

. Pull Pipe. Order 250 sks 65/35 poz 8% gel 500 lbs. hulls. Halliburton Cement Co.

Rush Water Trucks.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:20AM Day: 17 Month: July Year: 19 90

ACTUAL PLUGGING REPORT

Sand back to 3676 w/4 sks common cemen on sand w/
bailer. Rec. 2600 of casing. Sq 8 5/8 w/250 sks cement blend w/500 lbs.
hulls mixed in to max psi 1000 lbs. Close in psi 500 lbs. Plug complete.

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 06 2008

Remarks: (If additional description is necessary, use BACK of this form.) CONSERVATION DIVISION WICHITA, KS

I (did /xxdixxxx+) observe this plugging.

Handwritten initials/signature

Signed Carl Goodrow (TECHNICIAN)