

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Rama Operating Co., Inc.
Address: P.O. Box 159 Stafford, KS. 67578
Phone: (620) 234-5191 Operator License #: 3911
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 10-8-2007 (Date)
by: Richard Lacey (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Viola Depth to Top: 3852 Bottom: 3860 T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-185-20,834-00-00
Lease Name: Knoche Verle KCC Pkt Per CP213
Well Number: 1
Spot Location (QQQQ): 100' - S - Ne - Ne
4520 Feet from North / South Section Line
780 Feet from East / West Section Line
Sec. 8 Twp. 24 S. R. 12 East West
County: Stafford
Date Well Completed: 9-6-1978
Plugging Commenced: 7-14-08
Plugging Completed: 7-15-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	290	0
				4 1/2	4,036	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP @ 3,800 w/ 3 Sk: 1st Plug 2,500' W/ 25 sks.; 2nd Plug @ 950' to surface, lost circulation, Stated pumping down 8 5/8 would not pressure. SION. Tagged cement @ 867'; Perf. @ 330"; Circ. 75 sks thru tubing to surface. Pulled tubing, pumped 75 sks down casing circulated out of 8 5/8. Held pressure.

Name of Plugging Contractor: Basic Energy Services License #: 32453 34069 RECEIVED
Address: P.O. Box 8613 Pratt, Ks 67124 KANSAS CORPORATION COMMISSION


Name of Party Responsible for Plugging Fees: Rama Operating Co., Inc JUL 21 2008

State of Kansas County, Stafford, ss. CONSERVATION DIVISION
Robin L. Austin of Rama Operating Co., Inc. WICHITA, KS
(Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) _____

(Address) P.O. Box 159 Stafford, Ks. 67578



SUBSCRIBED and SWORN TO before me this 16th day of July, 20 08
Dawn Schreiber My Commission Expires: 5-1-11
Notary Public