

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD

K.A.R. 82-3-117

Form CP-4 September 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Anadarko Petroleum Corporation

Address: PO Box 1330 Houston, TX 77251-1330

Phone: (832) 636-8380 Operator License # 4549

Type of Well: ENHR Docket # E-26115 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 06/10/2008 (Date)

by: Eric McClaren (KCC District Agent's)

Is ACO-1 filed? [x] Yes [] No If not, is well log attached? [] Yes [] No

Producing Formation(s): List All (If needed attach another sheet)

Chester Depth to Top: 6122 Bottom: 6240 T.D. 6380

Depth to Top: Bottom: T.D.

Depth to Top: Bottom: T.D.

API Number 15- 175-20659 - 00 00

Lease Name Hitch Unit

Well Number 5-1 KCC PRT PEN

Spot Location (QQQQ) NW E NW SW

2022 1980 Feet from [] North / [x] South Line of Section

4741 660 Feet from [x] East / [x] West Line of Section

Sec. 11 Twp. 33 S. R. 34 [] East [x] West

County: Seward

Date Well Completed: 02/02/1983

Plugging Commenced: 06/17/2008

Plugging Completed: 06/18/2008

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put in, Pulled out). Rows show data for 0 to 6379' depths with casing sizes of 8-5/8" and 5-1/2".

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.

Mixed 300 lbs hulls & 25 sks cmt pump plug from 6122' to 5922'. Shot & pulled 5-1/2 to 1660'. Circ hole w/mud & mixed 50 sk cmt plug from 1660' to 1510'. Pulled 5-1/2 to 600' & mixed 40 sk cmt plug from 600' to 480'. Pulled 5-1/2 to 40' & mixed 10 sk plug from 40' to 0'. Cut off & Capped 8-5/8" 3' below ground level.

Name of Plugging Contractor: Sargent and Horton Plugging, Inc. License # 31151


Address Rt. 1 Box 49BA Tyrone, OK 73951-9731

Name of Party Responsible for Plugging Fees: Anadarko Petroleum Corporation

State of Texas County, Montgomery, ss.

Diana Smart Staff Regulatory Analyst (Employee of Operator) or (Operator) on above-described well, first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well as filed and the same are true and correct, so help me God.



(Signature) Diana Smart

(Address) PO Box 1330 Houston, TX 77251-1330

SUBSCRIBED and SWORN TO before me this 28th day of July, 2008

(Signature) Pamela C. Frye My Commission Expires: 3/17/09 Notary Public

RECEIVED KANSAS CORPORATION COMMISSION

JUL 29 2008

CONSERVATION DIVISION WICHITA, KS

Handwritten initials/signature in bottom right corner.