

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD

K.A.R. 82-3-117

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Anadarko Petroleum Corporation
 Address: PO Box 1330 Houston, TX 77251-1330
 Phone: (832) 636-8380 Operator License # 4549
 Type of Well: ENHR Docket # E-26115
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (if SWD or ENHR)
 The plugging proposal was approved on: 06/10/2008 (Date)
 by: Eric McClaren (KCC District Agent's)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
Chester Depth to Top: 6140' Bottom: 6210' T.D. 6500'
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number 15- 175-20531 -00-00
 Lease Name Hitch Unit
 Well Number 1-6 *KCC PRT 201 CP 2/3*
 Spot Location (QQQQ) _____ NW _____ SE _____ NW _____
 _____ 3372 Feet from North / South Line of Section
 _____ 3356 Feet from East / West Line of Section
 Sec. 3 Twp. 33 S. R. 34 East West
 County: Seward
 Date Well Completed: 09-15-1981
 Plugging Commenced: 07/22/2008
 Plugging Completed: 07/24/2008

Show depth and thickness of all water, oil and gas formations.


Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put in	Pulled out
		0	1642'	8-5/8"	1642'	0
		0	6475'	5-1/2"	6475'	3028', 2428', 2302', 1802'
						csg finally loose @ 1802'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Mixed 300 lbs hulls & 25 sks cmt pump plug from 6140' to 5940'. Shot & pulled 5-1/2 to 1670'. Circ hole w/mud & mixed 50 sk cmt plug from 1670' to 1520'. Pulled 5-1/2 to 600' & mixed 40 sk cmt plug from 600' to 480'. Pulled 5-1/2 to 40' & mixed 10 sk plug from 40' to 0'. Cut off & Capped 8-5/8" 3' below ground level.

Name of Plugging Contractor: Sargent and Horton Plugging, Inc. License # 31151
 Address Rt. 1 Box 49BA Tyrone, OK 73951-9731
 Name of Party Responsible for Plugging Fees: Anadarko Petroleum Corporation **JUL 29 2008**
 State of Texas County, Montgomery, SS. CONSERVATION DIVISION
Diana Smart Staff Regulatory Analyst (Employee of Operator) or (Operator) on above-described well, being first duly
 WICHITA, KS

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well as filed and the same are true and correct, so help me God.



(Signature) Diana Smart
 (Address) PO Box 1330 Houston, TX 77251-1330

SUBSCRIBED and SWORN TO before me this 28th day of July, 2008

Pamela A Frye My Commission Expires: 3/17/09
 Notary Public