

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

K.A.R. 82-3-117

Lease Operator: Anadarko Petroleum Corporation
 Address: PO Box 1330 Houston, TX 77251-1330
 Phone: (832) 636-8380 Operator License # 4549
 Type of Well: ENHR Docket # E-26115
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: 06/10/2008 (Date)
 by: Eric McClaren (KCC District Agent's)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
Chester Depth to Top: 6094 Bottom: 6171 T.D. 6290
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number 15- 175-20655 - 00 - 00
 Lease Name Hitch Unit
 Well Number 1-12
 Spot Location (QQQQ) C SW SE SE
408 Feet from North / South Line of Section
1102 Feet from East / West Line of Section
 Sec. 3 Twp. 33 S. R. 34 East West
 County: Seward
 Date Well Completed: 11/02/1982
 Plugging Commenced: 07/08/2008
 Plugging Completed: 07/09/2008

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put in	Pulled out
		0	1620'	8-5/8"	1620'	0
		0	6280'	5-1/2"	6280'	4025' 3004'
						KCC Pkt P-14 07/2/13

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Mixed 300 lbs hulls & 25 sks cmt to set plug from 6094' to 5894'. Shot & pulled 5-1/2 to 1650'. Circ hole w/mud & mixed 50 sk cmt plug from 1650' to 1500'. Pulled 5-1/2 to 600' & mixed 40 sk cmt plug from 600' to 480'. Pulled 5-1/2 to 40' & mixed 10 sk plug from 40' to 0'. Cut off & Capped 8-5/8" 3' below ground level.

Name of Plugging Contractor: Sargent and Horton Plugging, Inc. License # 31151
 Address Rt. 1 Box 49BA Tyrone, OK 73951-9731
 Name of Party Responsible for Plugging Fees: Anadarko Petroleum Corporation
 State of Texas County, Montgomery, ss.
Diana Smart Staff Regulatory Analyst (Employee of Operator) or (Operator) on above-described well, Wichita, KS

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 28 2008


sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) Diana Smart

(Address) PO Box 1330 Houston, TX 77251-1330

SUBSCRIBED and SWORN TO before me this 25th day of July, 20 08

Bertha Neefe My Commission Expires: 12-27-09
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten initials]