

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD

K.A.R. 82-3-117

Form CP-4  
September 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Anadarko Petroleum Corporation  
 Address: PO Box 1330 Houston, TX 77251-1330  
 Phone: (832) 636-8380 Operator License # 4549  
 Type of Well: Oil Docket # \_\_\_\_\_  
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
 The plugging proposal was approved on: 06/10/2008 (Date)  
 by: Eric McClaren (KCC District Agent's)  
 Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
 Producing Formation(s): List All (If needed attach another sheet)  
Chester Depth to Top: 6140 Bottom: 6190 T.D. 6336  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number 15- 175-21281 -00-00  
 Lease Name Hitch Unit  
 Well Number 1-11A *KCC ACT 001 OPS.*  
 Spot Location (QQQQ) nw nw se  
e NE SW SE  
1057 1000 Feet from  North /  South Line of Section  
1316 1250 Feet from  East /  West Line of Section  
 Sec. 3 Twp. 33 S. R. 34  East  West  
 County: Seward  
 Date Well Completed: 12/27/1992  
 Plugging Commenced: 07/09/2008  
 Plugging Completed: 07/10/2008

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put in	Pulled out
		0	1622'	8-5/8"	1622'	0
		0	6313'	5-1/2"	6313'	3024'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Mixed 300 lbs hulls & 25 sks cmt to set plug from 6140' to 5940'. Shot & pulled 5-1/2 to 1650'. Circ hole  
w/mud & mixed 50 sk cmt plug from 1650' to 1500'. Pulled 5-1/2 to 600' & mixed 40 sk cmt plug from 600' to 480'.  
Pulled 5-1/2 to 40' & mixed 10 sk plug from 40' to 0'. Cut off & Capped 8-5/8" 3' below ground level.

Name of Plugging Contractor: Sargent and Horton Plugging, Inc. License # 31151  
 Address Rt. 1 Box 49BA Tyrone, OK 73951-9731

RECEIVED  
KANSAS CORPORATION COMMISSION

Name of Party Responsible for Plugging Fees: Anadarko Petroleum Corporation  
 State of Texas County, Montgomery, ss.  
Diana Smart Staff Regulatory Analyst (Employee of Operator) or (Operator) on above-described well, being first duty

JUL 28 2008

CONSERVATION DIVISION  
WICHITA, KS


sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) Diana Smart

(Address) PO Box 1330 Houston, TX 77251-1330

SUBSCRIBED and SWORN TO before me this 25th day of July, 20 08

Bertha Neff My Commission Expires: 12-27-09  
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*ACT*