

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD

K.A.R. 82-3-117

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Anadarko Petroleum Corporation
Address: PO Box 1330 Houston, TX 77251-1330
Phone: (832) 636-8380 Operator License # 4549
Type of Well: Oil Docket # _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 06/10/2008 (Date)
by: Eric McClaren (KCC District Agent's)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Chester Depth to Top: 6149 Bottom: 6195 T.D. 6420
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number 15- 175-20625 - 90 - 60
Lease Name Hitch Unit
Well Number 1-8
Spot Location (QQQQ) W2 SW SW NE
2310 Feet from North / South Line of Section
2540 Feet from East / West Line of Section
Sec. 3 Twp. 33 S. R. 34 East West
County: Seward
Date Well Completed: 04/24/1982
Plugging Commenced: 07/17/2008
Plugging Completed: 07/18/2008

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put in	Pulled out
		0	1643'	8-5/8"	1643'	0
		0	6396'	5-1/2"	6396'	3039'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Mixed 300 lbs hulls & 25 sks cmt pump plug from 6149' to 5949'. Shot & pulled 5-1/2 to 1670'. Circ hole w/mud & mixed 50 sk cmt plug from 1670' to 1520'. Pulled 5-1/2 to 600' & mixed 40 sk cmt plug from 600' to 480'. Pulled 5-1/2 to 40' & mixed 10 sk plug from 40' to 0'. Cut off & Capped 8-5/8" 3' below ground level.

Name of Plugging Contractor: Sargent and Horton Plugging, Inc. License # 31151
Address Rt. 1 Box 49BA Tyrone, OK 73951-9731
Name of Party Responsible for Plugging Fees: Anadarko Petroleum Corporation
State of Texas County, Montgomery, ss.
RECEIVED
KANSAS CORPORATION COMMISSION
JUL 28 2008


Diana Smart Staff Regulatory Analyst (Employee of Operator) or (Operator) on above-described well, who is duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) Diana Smart
(Address) PO Box 1330 Houston, TX 77251-1330

SUBSCRIBED and SWORN TO before me this 25th day of July, 2008

Bertha Nefe My Commission Expires: 12-27-09
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten initials]