

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD

K.A.R. 82-3-117

Form CP-4 September 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Anadarko Petroleum Corporation
Address: PO Box 1330 Houston, TX 77251-1330
Phone: (832) 636-8380 Operator License # 4549
Type of Well: ENHR Docket # E-26115
The plugging proposal was approved on: 06/10/2008
by: Eric McClaren (KCC District Agent's)
Is ACO-1 filed? [X] Yes [] No
Producing Formation(s): Chester Depth to Top: 6098 Bottom: 6108 T.D. 6330

API Number 15- 175-20466 -00-01
Lease Name Hitch Unit
Well Number 1-3
Spot Location (QQQQ) C SW SE
835 660 Feet from [] North / [X] South Line of Section
1947 1980 Feet from [X] East / [] West Line of Section
Sec. 3 Twp. 33 S. R. 34 [] East [X] West
County: Seward
Date Well Completed: 05/29/1980
Plugging Commenced: 07/10/2008
Plugging Completed: 07/15/2008

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put in, Pulled out). Rows show casing data for 8-5/8" and 4-1/2" pipes.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

Mixed 150 lbs hulls & 20 sks cmt to set plug from 6098' to 5898'. Shot & pulled 4-1/2 to 1660'. Circ hole w/mud & mixed 50 sk cmt plug from 1660' to 1510'. Pulled 4-1/2 to 600' & mixed 40 sk cmt plug from 600' to 480'. Pulled 4-1/2 to 40' & mixed 10 sk plug from 40' to 0'. Cut off & Capped 8-5/8" 3' below ground level.

Name of Plugging Contractor: Sargent and Horton Plugging, Inc. License # 31151
Address Rt. 1 Box 49BA Tyrone, OK 73951-9731
Name of Party Responsible for Plugging Fees: Anadarko Petroleum Corporation
State of Texas County, Montgomery, ss.

RECEIVED KANSAS CORPORATION COMMISSION

JUL 28 2008

CONSERVATION DIVISION

Diana Smart Staff Regulatory Analyst (Employee of Operator) or (Operator) on above-described well

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) Diana Smart

(Address) PO Box 1330 Houston, TX 77251-1330

SUBSCRIBED and SWORN TO before me this 25th day of July, 2008

Bertha Neff Notary Public My Commission Expires: 12-27-09



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT