

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Samson Resources Company
Address: 2 West Second Street
Phone: (918) 583-1791 Operator License #: 33966
Type of Well: P&A DH KCC PCT PNC PZ 13 N/A Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: March 9th, 2008 (Date)
by: Steve Durant (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
N/A Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-187-21119-00-00
Lease Name: Bobwhite
Well Number: 1-35
Spot Location (QQQQ): S/2 - NE - SE - SW
800 Feet from North / South Section Line
2310 Feet from East / West Section Line
Sec. 35 Twp. 28 S. R. 41 East West
County: Stanton
Date Well Completed: N/A
Plugging Commenced: 3-9-08
Plugging Completed: 3-10-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
L. Morrow Keyes @ 5472' - 50' Thick	Water	Surface	1706'	8 5/8"		N/A
St. Louis @ 5644' - 10' Thick	Water					

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Mud Properties Left in Hole: 8.8 ppg MW; 58 Vis

Halliburton Cement: 40/60 Pos/Premium w/ 4% gel @ 13.5 ppg; 1.52 yield

Plug #1: 50 sx @ 1742' Plug #2: 50 sx @ 753' Plug #3: 20 sx @ 60'

Plug Rat & Mouse Holes

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 28 2008

Name of Plugging Contractor: Trinidad Drilling Limited Partnership License #: 33784

Address: 3728 West Jones Ave; Garden city, KS 67846

CONSERVATION DIVISION
WICHITA, KS

Name of Party Responsible for Plugging Fees: Samson Resources Company

State of Oklahoma County, Tulsa, ss.

Erik Block (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) Erik Block

(Address) 2 West Second Street; Tulsa, OK 74103

SUBSCRIBED and SWORN TO before me this 18th day of April

Luci J. Spain
Notary Public

My Commission Expires: _____



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202