

Baxter A2
 NW/4 of Sec 2-9S-16#
 Rooks County, Kansas
 Broadview Oil Company

Casing Record:

8 5/8" O.D. Surface Casing set at
 100' and cemented with 75 sacks of
 cement

Commenced: April 11, 1941
 Completed: April 29, 1941

Surface soil and shale	0	70
Shale and lime	70	100
Shale	100	530
Shale, sand and shells	530	1160
Shale	1160	1290
Anhydrite	1290	1328
Shale and shells	1328	1760
Shale and lime	1760	2110
Broken lime	2110	2345
Shale and lime	2345	2535
Shale and lime shells	2535	2640
Shale and lime	2640	2780
Lime	2780	2785
Sand	2785	2810
Shale, sand and lime	2810	2930
Lime	2930	2970
Shale	2970	3000
Lime and shale	3000	3065
Lime	3065	3097
Shale	3097	3123
Lime	3123	3136
Shale	3136	3146
Lime	3146	3189
Lime, medium	3189	3197
Lime, broken	3197	3198
Lime, hard	3198	3202
Lime, medium	3202	3205
Lime, hard	3205	3219
Lime, broken	3219	3224
Lime, hard	3224	3226
TOTAL DEPTH	3226	

Lime (show oil)	3186	3191
Shale (blue, red)	3191	3193
White Lime	3193	3219
Shale (blue, red)	3219	3221
Pay	3221	3222
Hard Lime	3222	3224

3000 gals. acid	3212
Total depth	3224
Elevation	2001
Pipe set at	3186