


Max Cohen

Company (VICKERS PETROLEUM CO., INC.)
Farm - Gamble No. 4

15-163-03592-00-00
SEC. 3 T. 9 R. 16W
NW SW NW

Total Depth. 3424'
Comm. 5-20-48 Comp. 6-21-48
Shot or Treated. Acidized
Contractor.
Issued. 7-24-48

County. Rooks
KANSAS



Elevation. 1966 RF.

Production. Est. 50 BO & 35 BWPD

CASING:

8-5/8" 74' Cem. w/ 40 sx
5-1/2" 3424' Cem. w/40 sx

Figures Indicate Bottom of Formations.

surface	0-74
shale	355
shale & sand	940
shale & red bed	1125
red bed & shale	1255
anhydrite	1285
shale & shells	1620
salt, shale & shells	1670
shale & lime	1940
lime brkn	2225
lime	2330
lime brkn	2395
lime	2455
shale & lime	2600
shale	2710
lime & shale	2975
lime	3005
shale & lime	3058
lime	3066
shale	3077
lime	3340
shale & some lime	3416
conglomerate	3418
dolomite	3424
Total Depth	

Lane Wells Plug @ 3391
 Ran Lane Wells Radioactivity Log
 Perforated 36 shots 3261-3276
 2000 gal. acid, test 2 bbls
 fluid per hour.
 Lane Wells Plug @ 3255' top
 Perforate 36 shots 3176-3184
 3000 gal. acid test. 2 1/4 bbls fluid
 per hour 50% water.
 Perforate 36 shots 3116-3127
 Perforate 35 shots 3238-3248
 2000 gal. acid 3116-3127
 2000 gal. acid 3238-3248
 Drill out Lane Wells Plug. Put
 on pump.

Tops:
 Lansing 3075
 Base K. C. 3310
 Conglomerate Chert 3414
 Arbuckle 3416