

ROTARY DRILLER'S LOG

E. K. Carey Contractor  
 Box 620  
 McPherson, Kansas

Elevations: 2308 K.B.  
 2306 D.F.  
 2303 Gr.

Miron Goff #2

8-5/8" x 4 1/2" Head 6.40'  
 below K. B.

C, S/2 SW SW  
 Sec. 3-8-24W  
 Graham County, Kansas

Casing Record:

Well Commenced: 5-13-54  
 Well Completed: 5-26-54

8-5/8" @ 130' W/85 sks.  
 4-1/2" 3774' W/125 " or  
 1' off bottom.

Contractor: E. K. Carey, Contractor, Rig #1, Box-620, McPherson, Kansas  
 Geologist: Roger Welty, Hill City, Kansas

Figures Indicate Bottom of Formation K. B.

Base and cellar	7
Shale	126
Shells	130
Shale and shells	1380
Sand	1390
Shale and red bed	1530
Sand and shale	1700
Shale and shells	1725
Anhydrite	1985
Red bed and shale	2215
Shale and shells	2445
Shale and lime	3045
Shale and shells	3138
Shale and lime	3215
Lime and shale	3519
Lime	3764
Lime and shale	3775 TD

Geologist Tops:

Top Lansing	3535 (-1227)
1st. Pay	3696 to 3701 (-1389)
2nd. Pay	3708 to 3721 (-1400)
3rd. Pay	3726 to 3742 (-1418)
R.T.D.	3775 (-1467)

Set 4 1/2" casing 3774 or 1' off bottom.

DST - 3721, packer set 3702, tool open 1 hr. strong blow. Closed for 20 min. BHP. Rec. 1591' of oil; gas to surface in 1 hr., 15 min. BHP 540#.

This is to certify that the above information is to the best of my knowledge true and correct.

SUBSCRIBED AND SWORN to before me this 27th day of May, 1954

**RECEIVED**  
 STATE CORPORATION COMMISSION

MAR 18 1955

*3/18/55*

CONSERVATION DIVISION  
 Wichita, Kansas

E. K. CAREY CONTRACTOR

BY

*Herbert Rhoton*

Herbert Rhoton, Superintendent

*[Signature]*

NP

My Commission Expires: November 13, 1956.