

ROTARY DRILLER'S LOG

E. K. Carey Contractor
Box 620
McPherson, Kansas

Elevations: 2332 K. B.
2330 D. F.
2328 Gr.

Miron Goff #1

8-5/8" x 5 1/2" Head 6.20'
below K. B.

NW SW SW
Sec. 3-8-24W
Graham County, Kansas

Casing Record:

Well Commenced: 2-12-54
Well Completed: 2-26-54

8-5/8" @ 166' w/85 sks.
Portland cement & 100# cc.
5-1/2" @ 3799' w/100 sks.
Pozmix.

Contractor: E. K. Carey Contractor, Rig #1, Box 620, McPherson, Kansas
Geologist: Don Hollar, E. K. Carey Drlg. Co. 815 Central Bldg. Wichita

Figures Indicate Bottom of Formation K. B.

Cellar	7
Shale	165
Shells	166
Shale	1320
Shale and shells	1950
Lime and shale	2170
Red rock and shale	2257
Lime and shale	2325
Shale w/lime stks.	2570
Shale and lime	2870
Lime	3085
Lime and shale	3380
Lime w/shale stks.	3514
Lime and shale breaks	3530
Lime	3800 TD

Geologist Tops:

Heebner	3539
Lansing	3559
Bs. K.C.	3780
Rotary Total Depth	3800

5 1/2" Casing set 3799'
Centralizers @ 3787, 3745 & 3700'.

DST - 3726', Packer set 3710 or 16'
anchor. Tool open 1 hr. blow in-
creased for 20 M. then steady for 40 M.
Recovered 200' gas 80' muddy oil,
20M. BHP 1150#.

DST - 3724 to 45' or 21' anchor. Tool
open 1 hr. Recovered 2460' oil, gas
to surface in 45 M. 20 M. BHP 1010#
IFF 360# FFP 880#.

DST - 3762', Packer set 3751 or 11'
anchor. Tool open 1 hr. Recovered
600' gas and 145' of clean oil, no
water. 20 M. BHP 1100#.

This is to certify that the above information is to the best of my
knowledge true and correct.

E. K. CAREY CONTRACTOR

BY Herbert Rhoton
Herbert Rhoton, Superintendent

Admission

NP

My Commission Expires: November 13, 1956

RECEIVED
STATE CORPORATION COMMISSION
APR 29 1986
CONSERVATION DIVISION
Wichita, Kansas