


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Butler County. Sec. 3 Twp. 26 Rge. 3 E E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines \_\_\_\_\_  
C N/2 SW SW  
Lease Owner Charles Carlock  
Lease Name Wait Well No. 2  
Office Address 1515 Hillcrest, Newton, Kansas 67114  
Character of Well (Completed as Oil, Gas or Dry Hole) oil



Locate well correctly on above  
Section Plat

Date Well completed 10-21 1966  
Application for plugging filed 8-#3 1978  
Application for plugging approved 8-#4 1978  
Plugging commenced 8-9 1978  
Plugging completed 8-10 1978  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Don Thompson  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 2830  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		2284'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was-placed-and-the-method or methods-used in introducing it-into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set. Plugged off bottom of hole with sand. Sand from 2830' to 2790'. Dumped 5 sx of cement. Mudded hole to 230'. Made 15' of rock bridge. Dumped 3 Yrds. of Ready-Mix cement, filling to the bottom of the cellar.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 14 1978  
8-14-78  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Art Lamb Casing Pulling Inc.  
2809 King St. Hutchinson, Kansas 67501

STATE OF Kansas COUNTY OF Reno, ss.  
Art Lamb (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
2809 King St. Hutchinson, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of August, 1978

[Signature]  
Notary Public.

My commission expires April 18, 1982



STENCILED

KANSAS GEOLOGICAL SOCIETY  
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
KANSAS GEOLOGICAL SOCIETY BUILDING  
508 EAST MURDOCK - WICHITA, KANSAS

ORIGINAL

DEC 31 1966

COMPANY SeRoBee Drilling Co., Inc.

SEC. 3 T. 26 R. 3E  
LOC. C N/2 SW SW

FARM Wait NO. 2


TOTAL DEPTH 2795'  
COMM. 10-14-66

COMP. 10-21-66

COUNTY Butler

KANSAS

SHOT OR TREATED  
CONTRACTOR Se RoBee Drilling  
ISSUED 12-31-66



CASING

20 10  
15 8 5/8 200' W/200 SX  
12 6  
13 5 1/2 2795' W/80 SX

ELEVATION 1306 KB

PRODUCTION 55 BOPD PLUS WT  
(Miss 2726-46)

FIGURES INDICATE BOTTOM OF FORMATIONS

0 - 250	Lime
250 - 600	Lime & Shale
600 - 725	Lime
725 - 1015	Shale & Lime Shells
1015 - 2310	Shale & Lime
2310 - 2470	Lime
2470 - 2720	Lime & Shale
2720 - 2795	Lime

GEOLOGICAL TOPS: *Log*

QQ

KC	2261 (-955)
Bs/KC	2426 (-1120)
Cherokee	2648 (-1342)
Cong.	2700 (-1394)
Miss.	2720 (-1414)
T. D.	2795 (-1489) 2830'

I certify the above to be a true and correct copy of the driller's log and Geological Tops to the best of my knowledge and belief.

*Paul S. Septer*

Paul S. Septer

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 04 1978  
CONSERVATION DIVISION  
Wichita, Kansas