

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15-015-21,529 00-00

LEASE NAME PARSLEY

TYPE OR PRINT

PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.

WELL NUMBER 4

SPOT LOCATION NE NW. SE

LEASE OPERATOR UNITED PETROLEUM INC.

SEC. 3 TWP. 26 RGE. 3e (E) OR (W)

ADDRESS P.O. BOX 63066 WICHITA, KS. 67203-0066

COUNTY BUTLER

PHONE # (316) 263-4027 OPERATORS LICENSE NO. 5048

DATE WELL COMPLETED 10-13-80

CHARACTER OF WELL OIL
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

PLUGGING COMMENCED 10-5-83

PLUGGING COMPLETED 10-10-83

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? YES

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? DIST. #2

IS ACC-1 FILED? IF NOT, IS WELL LOG ATTACHED? YES

PRODUCING FORMATION DEPTH TO TOP BOTTOM T.D. 2760'

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				4 1/2"		2,120.10'

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET. SANDED BACK TO 2670' WITH 4 SACKS OF CEMENT.

MUDDERED HOLE TO 250' MADE 15' ROCK BRIDGE AND FILLED WITH 4 YARDS OF READY MIX.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)


NAME OF PLUGGING CONTRACTOR H&H CASING PULLING CO. LICENSE No. 6053
ADDRESS 1427 N. HALSTEAD HUTCHINSON, KS. 67501

STATE OF KANSAS COUNTY OF RENO, SS.

DONALD H. HURST (EMPLOYEE OF OPERATOR) OR (OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.

(SIGNATURE) Donald H. Hurst
FINEST MOBILE HOME PARK LOT 78
(ADDRESS) GREAT BEND, KS. 67530

SUBSCRIBER AND SWORN TO BEFORE ME THIS 10th DAY OF October, 1983



Madeline Hurst
NOTARY PUBLIC

MY COMMISSION EXPIRES:

RECEIVED
STATE CORPORATION COMMISSION

OCT 12 1983
10-12-83
CONSERVATION DIVISION
Wichita, Kansas

FORM CP-4
REVISED 06-83

WELL COMPLETION REPORT AND DRILLER'S LOG

S. 3 T. 26 R. 3 E
 Loc. S.S. W of NE 1/4 SE X

API No. 15 - 015 - 21,529 X
 County Number

County BUTLER
 640 Acres
 N

Operator UNITED PATRUBENM, INDIAN

Address 924 N. MAIN WICHITA, KANSAS


Well No. # 4 Lease Name TROSBLEY

Footage Location 330 feet from (N) (S) line feet from (E) (W) line 990

Principal Contractor RPEX DRILLING Geologist F.W. MURGOON

Spud Date 10-2-80 Date Completed 10-13-80 Total Depth 2760 P.B.T.D.

Directional Deviation Oil and/or Gas Purchaser



Elev.: Gr. 1286
 DF 1289 KB 1291

CASING RECORD

Report of all strings set— surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Oil		8 5/8"		200'		100	Common Cement
		7 1/2"		9 1/2' x 2758'		75	60-40 Puz-Mix

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			4		2721-2722

TUBING RECORD

Size	Setting depth	Packer set at
2 3/8"	2706	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production 11-16-80 Producing method (flowing, pumping, gas lift, etc.) Pumping

RATE OF PRODUCTION PER 24 HOURS	Oil (20) bbls.	Gas	Water	Gas-oil ratio
	20		50	

Disposition of gas (vented, used on lease or sold) Producing interval (s) RECEIVED STATE CORPORATION COMMISSION

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Driller's Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Driller's Logs will be an open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas.

OCT 12 1980
 CONSERVATION DIVISION
 WICHITA, KANSAS

Operator

United Petroleum Inc.

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWOW, ETC.:

Well No.

#4

Lease Name

Parsley

oil

S 3 T 26 R 3 E W

WELL LOG

Show all important zones of porosity and contents thereof; corred intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Lime & Shale	149	205		
Lime & Shale	205	569		
Lime & Shale	569	712		
Shale	712	991		
Shale	991	1050		
Lime	1050	1055		
Shale W/lime Stks	1055	1300		
Shale W/lime stks	1300	1418		
Lime	1418	1425		
Shale W/ lime stks	1425	1462		
Shale W/ lime stks	1462	1501		
Shale	1501	1636		
Shale w/ lime stks	1636	1946		
Lime	1946	2077		
Lime & Shale stks	2077	2145		
Lime & Shale stks	2145	2259		
Lime	2259	2390		
Lime & Shale	2390	2535		
Lime W/shale stks	2535	2580		
Shale	2580	2695		
Shale W/lime Stks	2695	2729		
Lime	2729	2760		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Richard P. Berry
Signature

President
Title

11-19-80
Date

RECEIVED
STATE CORPORATION COMMISSION

OCT 12 1983

CONSERVATION DIVISION
Wichita, Kansas