


15-015-19924-00-00

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Butler County. Sec. 4 Twp. 26 Rge. 3 (E) E (W)  
Location as "NE/CNW/SW" or footage from lines NW SE SW  
Lease Owner K.T. Wiedemann  
Lease Name Gertrude Rombold Well No. 3  
Office Address 127 1/2 W. Central, El Dorado, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 2-23-54 19  
Application for plugging filed 2-18-54 19  
Application for plugging approved 2-18-54 19  
Plugging commenced 2-18-54 19  
Plugging completed 2-23-54 19  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Lawrence Mathews, Jr.  
Producing formation Depth to top Bottom Total Depth of Well 2779 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4	86'	
				6 5/8	2761'	2530'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Dumped 15 sx cement on bottom  
Set Rock Bridge from 200' to 180'  
Set 10 sx cement from 180' to 154'  
10 sx. Magogel mud to 20'  
Set Rock Bridge to 18'  
5 sx cement to surface

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Beaumont Petroleum Co. - company tools  
Address El Dorado, Kansas

STATE OF KANSAS, COUNTY OF BUTLER, ss.  
Carl Hankenson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Carl Hankenson

SUBSCRIBED AND SWORN to before me this 25th day of March, 1954

My commission expires 12-5-55

24-7368-6 3-53-20M

(Address)

Notary Public.



PLUGGING  
FILE SEC 4 T-26 R-3E  
BOOK PAGE 16 LINE 17

MAR 26 1954  
3-26-54  
CONSERVATION DIVISION  
Wichita, Kansas

GERTRUDE ROMBOLD #3

Rotary T.D. 2761  
Comm. Rot. 9-21-51  
Comp. Rot. 10-1-51

NW SE SW  
Sec. 4-26-3E  
Butler County

Cable Tool T.D. 2779  
Comm. C.T. 10-17-51  
Comp. C.T. 2-23-54

Formations:  
Top K.C. 2314  
Base K.C. 2477  
T. Miss.Chert 2756 ?


Casing Record

10 3/4 Surface 86'  
6 5/8 Oil String 2761' Recovered 2530' Lapweld

FIGURES INDICATE BOTTOM OF FORMATION  
FRANKS ROTARY BUSHING 3'25" ABOVE GROUND

cellar	5
clay	7
shale-lime	35
lime-shale brks	400
lime	415
sand	427
lime-shale brks	680
shale-lime strks	830
shale-shells	1040
lime-shale	1086
shale-shells	1187
shale	1246
lime-shale brks	1280
shale	1355
lime	1375
shale-shells	1425
shale	1440
lime-shale brks	1815
shale-shells	2060
sandy lime	2076
lime	2210
shale	2314
lime	2477
shale	2620
shale-shells	2685
shale-lime	2745
shale	2756
lime-chert	2761 Rot. T.D.
<u>Cable Tool</u>	
Hvy dolomite	2779 T.D.

2-23-54  
Plugged & Abandoned



DIVISION