

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15 015 21,399-60-60

LEASE NAME DOTY

WELL NUMBER 1

990' Ft. from S Section Line

330' Ft. from E Section Line

SEC. 4 TWP. 26 SRGE. 3 (E) ~~or XXX~~

COUNTY Butler

Date Well Completed \_\_\_\_\_

Plugging Commenced 6/19/95

Plugging Completed 6/20/95

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Gobens United Petroleum Inc.

ADDRESS 3223 English, Wichita, Ks 67218

PHONE# (316) 686 0227 OPERATORS LICENSE NO. \_\_\_\_\_

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on June 20, 1995 (date)

by Mike Wilson (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 2780'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size   | Put In | Pulled out |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 8 5/8  | 200'   | 0          |
|           |         |      |    | 4 1/2" | 2780'  | 1449'      |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Strung tools into 2750' Plugged back with gravel to 2700'. Dump 4 sacks cement @ 2700'. Dug cellar. Rip 4 1/2" cs @ 1650' & 1449'. Pull 1449' of 4 1/2". Put rock bridge 300' to 280'. Run 273' 1" pipe. United circulated 112 sacks, 60 40 pozmix cement + 2% gel from 273' to surface. Pull 1" pipe. Rig down.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Dale Wilson / W.W. Drilling Co. License No. 6012

Address RR #3 Box 66, El Dorado, Kansas 67042

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: David S. Langston

STATE OF Kansas COUNTY OF Butler, ss.

Dale Wilson Drilling contractor (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Dale Wilson

(Address) RR #3 Box 66, El Dorado, Ks.

SUBSCRIBED AND SWORN TO before me this 26th day of June, 1995

My Commission Expires: \_\_\_\_\_



Notary Public