


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Butler County. Sec. 7 Twp. 26 Rge. 3 (E) X (XX)
Location as "NE/CNWxSWx" or footage from lines CN/2 NE SW
Lease Owner Reid Parker
Lease Name L. A. DeMoss Well No. 1
Office Address 1347 S. Washington Avenue
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed March 16 1971
Application for plugging filed April 21 1972
Application for plugging approved April 21 1972
Plugging commenced May 11 1972
Plugging completed May 25 1972
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ted Dewey and Eugene Graham
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2910' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	130'	none
				5 1/2"	2909'	1584'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dumped 4 sacks of cement with dump balor on bottom
Set rock bridge from 210' to 200', filled surface casing with redy-mix cement, to base of cellar

RECEIVED
STATE CORPORATION COMMISSION
6-12-72
JUN 12 1972

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Robert Self (609)
Address R.R. #4, Hutchinson, Kansas


STATE OF Kansas, COUNTY OF Reno, ss.
I Robert Self

(employer of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert Self
R.R. #4, Hutchinson, Kansas
(Address)

Subscribed and sworn to before me this 4 day of June, 1972

My commission expires October 18, 1973
Notary Public



P

Company: Gulf & Interstate Oil Company Sec. 7 T. 26S R. 3E
 Farm: L.A. DeMoss No. 1 Loc. C N/2 NE SW
 Total Depth: 2910' County: Butler
 Comm. 1-13-71 Comp. 1-20-71

Contractor: Triangle Drilling Company

Surface Casing: 8-5/8" - 200' W/90 Sacks
 Oil String: 4-1/2" 2909' W/150 "

Elev: 1356' KB
 1353' DF
 1351' GL

Production: 6 BOPD + 900 BWPD

Figures Indicate Bottom Of Formations

0	200	Shale and lime
200	1000	Shale with lime streaks
1000	1610	Lime and shale
1610	2245	Lime and shale
2245	2355	Lime
2355	2520	Lime and shells
2520	2782	Shale and Sandy Limestone
2782	2792	Cong. Sand.
2792	2796	Cong. Chert
2796	2802	Mississippian Dolomite
2802	2831	Chert and Dolomite
2831	2850	Mississippian Chert
2850	2910	Mississippian Lime
2910		Total Depth

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 10 1972
 CONSERVATION DIVISION
 Wichita, Kansas

Formation Tops:	Kansas City	2355'	Sub Sea Datum	- 999
	B/KC	2520'		- 1164
	Cong. Sd.	2782'		- 1426
	Cong. Chert	2792'		- 1436
	Miss. Chert	2796'		- 1440
	Miss. Dol.	2802'		- 1446
	Chat Pay	2831'		- 1475
	Miss. Lime	2850'		- 1494
	Total Depth	2910'		- 1554

I certify the above to be a true and correct copy of the geological formation from the driller's logs to the best of my knowledge and belief.

Warren R. Winne
 Warren R. Winne - Gulf & Interstate Oil Co.