

Duane 8-15-86

15-015-19948-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER Completed 4-21-63

LEASE NAME Parks

WELL NUMBER 1

2970 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 8 TWP. 26 RGE. 3 (E) 01333

COUNTY Butler

Date Well Completed 4-21-63

Plugging Commenced 7-23-86

Plugging Completed 7-28-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Hess Oil Company

ADDRESS Box 905 McPherson, Kansas 67460

PHONE# (316) 241-4640 OPERATORS LICENSE NO. 5663

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? DIST. #2 3244 E. Douglas Wichita, KS 67208

Is ACO-1 filed? NO If not, is well log attached? YES

Producing Formation Mississippi Depth to Top 2783 Bottom? T.D. 2790

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Mississippi	Oil	150'	0	8 5/8"	4-16-63	
		2785'	0	4 1/2"	4-21-63	Pulled 750' (25 jts) 7-25-86

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Plugged back hole to 2745' w/pea gravel, set a cement plug w/5 sx common portland cement set on bottom with a dump bailer. Pulled & recovered 750' of 4 1/2" casing. Set a home made plug @ 260 and plugged back to 235' w/pea gravel. Cemented from 235 to surface with common sand cement.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Crawford Well Service License No. _____

Address El dorado, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.

James C. Hess (Employee of Operator) ~~or XXXXXXXXXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James C. Hess

(Address) James C. Hess

412 E. Douglas, Suite One
Wichita, Kansas 67202



AND SWORN TO before me this 29th day of July, 19 86

My Commission Expires: 10/13/86 Notary Public 7-30-86

Reports were made daily and as needed (due to problems) to the
KCC DIST. #2 3244 E. Douglas wichita, Kansas 67208.
(316) 651-5506

Plugging was supervised by Warren Kirkpatrick via phone.


KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **George Hess**
 FARM **Parks** NO. **1**

SEC. **8** T. **26S** R. **3E**
 LOC. **SE SE NE**

TOTAL DEPTH **2790'**
 COMM. **4-16-63** COMP. **4-21-63**
 SHOT OR TREATED
 CONTRACTOR **SeRoBee Drilling Co., Inc.**
 ISSUED

COUNTY **Butler**



CASING

20	10	
15	8	150' W/100 sacks
12	6	
13	5	4-2785' W/35 sacks

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

0	-	20	Clay - soil
20	-	70	Lime & shale
70	-	150	Lime
150	-	2330	Lime & shale
2330	-	2485	Lime
2485	-	2783	Lime & shale
2783	-	2790	Mississippi
		2790	TD

RECEIVED
STATE CORPORATION COMMISSION
CONS. DIV. WICHITA, KS

JUL 30 1986

100-100000-100000